



API# 15-015-24115-00-00

TICKET NUMBER 54353

LOCATION CL BORA, KS

FOREMAN Fuzz Y

PRESSURE PUMPING LLC  
PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

### FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-10-18	5033	T.W. 060 30-4	30	23	5	KS Butler
CUSTOMER Entravisco Energy LLC			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS P.O. Box 578			446	BRAD		
CITY Dewey			611	DJ		
STATE OKLA			725	FUZZY		
ZIP CODE 74029						

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 216' CASING SIZE & WEIGHT 8 5/8  
 CASING DEPTH 216' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 14.5 SLURRY VOL 32.6 WATER gal/sk 6.5 CEMENT LEFT in CASING 20'  
 DISPLACEMENT 12.4 BBL DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting on C+G Data. Rig up and establish circulation pump 10 BBL water, mix 135 SKS class 'A' 300cc, 250cc w/ 1/2# Poly Gluc. Displace 12 1/2 BBL and shut in.  
cement did circulate approx 6 BBL to pit

Thanks Fuzz Y  
Krew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500 <sup>00</sup>	1500 <sup>00</sup>
CE0002	20 miles	MILEAGE	715	143 <sup>00</sup>
CE0711	6.3 Ton	Ton mileage Delivery (min)	660 <sup>00</sup>	660 <sup>00</sup>
CC5900A	135 SKS	CLASS 'A'	20 <sup>00</sup>	2700 <sup>00</sup>
CC5325	400#	Calcium Chloride	125	500 <sup>00</sup>
CC5965	250#	Bentonite	130	75 <sup>00</sup>
CC6075	75#	Poly Gluc	2 <sup>00</sup>	150 <sup>00</sup>
		subtotal		5728 <sup>00</sup>
		discount	3590	2004 <sup>00</sup>
		subtotal		3723 <sup>00</sup>
		SALES TAX		
		ESTIMATED TOTAL		

AUTHORIZATION Butch Curmitt

TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





PRESSURE PUMPING LLC  
 PO Box 884, Chanute, KS 66720  
 620-431-9210 or 800-467-8676

## FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 54355  
 LOCATION EL Dorado, KS  
 FOREMAN Fuzz4

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																
12-13-18	5033	T. W. Wobe 30-04	30	23	5	Butler																
CUSTOMER CANTANSIO Energy LLC			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>TRUCK #</th> <th>DRIVER</th> <th>TRUCK #</th> <th>DRIVER</th> </tr> </thead> <tbody> <tr> <td>446</td> <td>Brind</td> <td></td> <td></td> </tr> <tr> <td>611</td> <td>Chance</td> <td></td> <td></td> </tr> <tr> <td>725</td> <td>Fuzz4</td> <td></td> <td></td> </tr> </tbody> </table>				TRUCK #	DRIVER	TRUCK #	DRIVER	446	Brind			611	Chance			725	Fuzz4		
TRUCK #	DRIVER	TRUCK #					DRIVER															
446	Brind																					
611	Chance																					
725	Fuzz4																					
MAILING ADDRESS P.O. Box 578																						
CITY Dewey	STATE OKLA	ZIP CODE 74029																				

JOB TYPE Production HOLE SIZE 7 7/8 HOLE DEPTH 2600' CASING SIZE & WEIGHT 5 1/2 15.5  
 CASING DEPTH 2582 3/4 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 14.4 SLURRY VOL 60 BBLs WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 61.5 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting on CTG Dalg Rig up and establish circulation  
Pump 5 BBL water, 5 BBL water (1SK), 5 BBL water, 10 BBL sodium metasilicate  
water (2 SKS) 5 BBL water, mix 10 SKS cement in RH, mix 210 SKS  
CLASS 'A' 4%<sup>000</sup>, 2%<sup>000</sup>, with 5# Kalsol/5K and 1/2 # Phenoseal/5K,  
Wash pump and lines. Dip plug and displace 6 2 1/4 BBL, 1000' 1.5K  
Land plug @ 1300' Floathold.

THANKS Fuzz4 & CREW

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0451	1	PUMP CHARGE	1900 <sup>00</sup>	1900 <sup>00</sup>
CE0002	20 miles	MILEAGE	7 <sup>13</sup>	143 <sup>00</sup>
CE0711		Tow mileage (min)	660 <sup>00</sup>	660 <sup>00</sup>
CC5000A	220 SKS	CLASS 'A'	20 <sup>00</sup>	4400 <sup>00</sup>
CC5325	400 #	Calcium Chloride	1 <sup>25</sup>	500 <sup>00</sup>
CC5965	850 #	Bentonite	.30	255 <sup>00</sup>
CC6077	1100 #	Kal-seal	.50	550 <sup>00</sup>
CC6079	120 #	Phenoseal	1 <sup>35</sup>	162 <sup>00</sup>
CC5970	100 #	Sodium metasilicate } flush	2 <sup>55</sup>	255 <sup>00</sup>
CC5325	50 #	Calcium Chloride }	1 <sup>25</sup>	62 <sup>50</sup>
CP3179	1	5 1/2" Plug	125 <sup>00</sup>	125 <sup>00</sup>
		sub total		9012 <sup>50</sup>
		discount		3154 <sup>31</sup>
		sub total		5858 <sup>19</sup>
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.