

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **4443**  
 Foreman David Gardner  
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
4-11-19	1313	Need #3 S.W.D.				Butler	KS
Customer MWK Petroleum Co.			Unit #		Driver		Unit #
Mailing Address 508 Stonelake Court			105		Jason		
City Augusta			113		Steve		
State KS							
Zip Code 67010							

Job Type Squeeze Hole Depth \_\_\_\_\_ Slurry Vol. 52 Bbl Tubing 2 3/8"  
 Casing Depth 2546' Hole Size 7 7/8" Slurry Wt. 15.6<sup>F</sup> Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2" Cement Left in Casing N/A Water Gal/SK 5.2 Other \_\_\_\_\_  
 Displacement 8 Bbl Displacement PSI 250 PSI Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting. Set RBP @ 2252' w/ 2 3/8" tubing, 4 1/2" casing, 2546'. Perfs 2324'-23  
Test RBP to 1450 PSI. Held good. Start pressure testing w/ tubing + PKR. Locate hole  
between 546'-672' + 672'-704'. Circulates to surface. Pull tubing + PKR. Dump 2 SKS  
on RBP. Dig out surface head to circulate. Establish injection rate w/ fresh water @  
2.7 BPM @ 150 PSI. Pump 10 Bbl fresh water ahead. Mixed 250 SKS Class 'H' Cement w/  
2% Cacle @ 15.6<sup>F</sup>/gal, yield 1.18 = 52 Bbl slurry. Good cement returns to surface in 4 1/2"  
annulus. Shut down. Wash out pump + lines. Displace w/ 8 Bbl fresh water @ 1.2 BPM +  
250 PSI. 10 Bbl good cement to pit. ISDP of 200 PSI. Held good. Shut well in. Job complete.  
Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C104	1	Pump Charge	1100.00	1100.00
C107	45	Mileage	4.20	189.00
C200	250 SKS	Class 'A' Cement	15.75	3,937.50
C205	470 <sup>#</sup>	Cacle @ 2%	.63	296.10
C108B	11.75 Tons	Ton Mileage - Bulk Truck	1.40	740.25
C223	160 <sup>#</sup>	Sand	.30	48.00
<i>Thank You</i>				
			Sub Total	6,310.85
			Less 5%	329.40
			6.5% Sales Tax	278.33

Authorization by Mike Kiser Title Owner Total 6,259.68

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.