



HURRICANE SERVICES INC


Customer	Quad Operating	Lease & Well #	Donley #38			Date	12/10/2018
Service District	Garnett, KS	County & State	Anderson, Ks		Legals S/T/R	Job #	ICT 1650
Job Type	Longstring	<input checked="" type="checkbox"/> PROD	<input type="checkbox"/> NJ	<input type="checkbox"/> SWD	New Well?	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> No
Equipment #	Driver	Job Safety Analysis - A Discussion of Hazards & Safety Procedures					
271	Kevin	<input checked="" type="checkbox"/> Hard hat	<input checked="" type="checkbox"/> Gloves	<input type="checkbox"/> Lockout/Tagout	<input type="checkbox"/> Warning Signs & Flagging		
241	Garrett	<input checked="" type="checkbox"/> H2S Monitor	<input checked="" type="checkbox"/> Eye Protection	<input type="checkbox"/> Required Permits	<input type="checkbox"/> Fall Protection		
	J.J	<input checked="" type="checkbox"/> Safety Footwear	<input type="checkbox"/> Respiratory Protection	<input type="checkbox"/> Slip/Trip/Fall Hazards	<input type="checkbox"/> Specific Job Sequence/Expectations		
77	Jake H	<input checked="" type="checkbox"/> FRC/Protective Clothing	<input type="checkbox"/> Additional Chemical/Acid PPE	<input type="checkbox"/> Overhead Hazards	<input type="checkbox"/> Muster Point/Medical Locations		
		<input checked="" type="checkbox"/> Hearing Protection	<input type="checkbox"/> Fire Extinguisher	<input type="checkbox"/> Additional concerns or issues noted below			
Comments							

Product/ Service Code	Description	Unit of Measure	Quantity	Net Amount	
c010	Cement Pump	ea	1.00	\$675.00	
m025	Ton Mileage- Minimum	each	1.00	\$240.00	
cp015	H-325	sack	100.00	\$1,600.00	
fe025	2 7/8" Rubber Plug	ea	2.00	\$64.00	
Customer Section: On the following scale how would you rate Hurricane Services Inc. ?					
		Net:			\$2,579.00

Based on this job, how likely is it you would recommend HSI to a colleague?	Total Taxable	\$ -	Tax Rate:		
<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>			State tax laws deem certain products and services used on new wells to be sales tax exempt. Hurricane Services relies on the customer provided well information above to make a determination if services and/or products are tax exempt.	Net:	
Unlikely 1 2 3 4 5 6 7 8 9 10 Extremly Likely	Sale Tax:	\$ -			
				Total:	\$ 2,579.00
HSI Representative: Jake Heard					

TERMS: Cash in advance unless Hurricane Services Inc. (HSI) has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts shall pay interest on the balance past due at the rate of 1 1/4% per month or the maximum allowable by applicable state or federal laws. In the event it is necessary to employ an agency and/or attorney to affect the collection, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount is immediately due and subject to collection. Prices quoted are estimates only and are good for 30 days from the date of issue. Pricing does not include federal, state, or local taxes, or royalties and stated price adjustments. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services. Any discount is based on 30 days net payment terms or cash. **DISCLAIMER NOTICE:** Technical data is presented in good faith, but no warranty is stated or implied. HSI assumes no liability for advice or recommendations made concerning the results from the use of any product or service. The information presented is a best estimate of the actual results that may be achieved and should be used for comparison purposes and HSI makes no guarantee of future production performance. Customer represents and warrants that well and all associated equipment in acceptable condition to receive services by HSI. Likewise, the customer guarantees proper operational care of all customer owned equipment and property while HSI is on location performing services. The authorization below acknowledges the receipt and acceptance of all terms/conditions stated above, and Hurricane has been provided accurate well information in determining taxable services.

X _____ **CUSTOMER AUTHORIZATION SIGNATURE**



CEMENT TREATMENT REPORT

Customer: **Quad Operating**
 City, State:
 Field Rep:

Well: **Donley #38**
 County: **Anderson, KS**
 S-T-R:

Ticket: **ICT 1650**
 Date: **12/10/2018**
 Service: **Longstring**

Downhole Information	
Hole Size:	5.875 in
Hole Depth:	922 ft
Casing Size:	2.875 in
Casing Depth:	916 ft
Tubing / Liner:	in
Depth:	ft
Tool / Packer:	
Depth:	ft
Displacement:	5.3 bbls

Slurry	
Weight:	14.5 # / sx
Water / Sx:	7.44 gal / sx
Yield:	1.49 ft³ / sx
Bbls / Ft.:	0.0255
Depth:	916 ft
Volume:	23.35 bbls
Excess:	%
Total Slurry:	26.53 bbls
Total Sacks:	100 sx

Cement Blend		
Product	%	#
Class A	100.0	9400
Gel	2.0	188
CaCl	3.0	282
Metso		
KolSeal		
PhenoSeal	.5 lb	50
Salt		
Total		9,920

TIME	RATE	PSI	BBLs	REMARKS	TIME	RATE	PSI	BBLs	REMARKS
				On location safety meeting					
				Spot in and rig up					
				Hook up to tubing					
	2.0	50.0	3.0	Break circulation					
	2.0	50.0	5.0	Pump mudflush					
	2.0	50.0	5.0	Pump dyed water					
	2.0	50.0	26.5	Mix and pump cement					
				Stop					
				Wash pump and lines					
				Drop plug					
	1.0	200.0	5.3	Displace					
		1,180.0		Bump plug					
				Shut in well					

CREW		UNIT	SUMMARY		
Cementer:			Average Rate	Average Pressure	Total Fluid
Pump Operator:			1.8 bpm	263.33 psi	44.80 bbls
Bulk #1:					
Bulk #2:					