

**SM Oil & Gas, Inc.**  
**P. O. Box 189**  
**Skiatook, Oklahoma 74070**  
620-725-3200

June 6, 2017

Kansas Corporation Commission  
Conservation Division  
266 N. Main Street – Suite #220  
Wichita, Kansas 67202-1513

**Re: Trust #6**  
**API #15-019-27580-00-00**  
**Cement Usage ACO-1**

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 12 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast  
Area Manager

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. **3346**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-9-17	1180	TRUST #6				CQ	Ks
Customer <u>S. M. OIL &amp; GAS INC.</u>			Safety Meeting <u>KM AM</u>	Unit #	Driver	Unit #	Driver
Mailing Address <u>P.O. Box 189</u>				<u>104</u>	<u>ALAN M.</u>		
City <u>SKIATOOK</u>				<u>112</u>	<u>ALLEN B.</u>		
State <u>OK</u>				<u>115</u>	<u>STEVE M.</u>		
Zip Code <u>74070</u>							

Job Type LONGSTRING Hole Depth 1620' Slurry Vol. 34 LEAD 20 TAIL Tubing \_\_\_\_\_  
 Casing Depth 1590' Hole Size 6 3/4" Slurry Wt. 12.8\* - 14\* Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 11.60\* Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 25 BBL Displacement PSI 1000\* Bump Plug to 1500 BPM \_\_\_\_\_

Remarks: SAFETY MEETING: RIG UP TO 4 1/2 CASING. BREAK CIRCULATION W/ 45 BBL FRESH WATER. PUMP 500\* GEL FLUSH W/ HULLS, 5 BBL WATER SPACE. MIXED 125 SKS 50/50 POZMIX CEMENT W/ 6% GEL, 1" PHENOSEAL /SK @ 12.8\*/GAL = 34 BBL SLURRY. TAIL IN W/ 75 SKS OWC CEMENT W/ 1" PHENOSEAL /SK @ 14\*/GAL = 20 BBL SLURRY. WASH OUT PUMP & LINES. SHUT DOWN. RELEASE PLUG. DISPLACE PLUG TO SEAT W/ 25 BBL FRESH WATER. FINAL PUMPING PRESSURE 1000 PSI. BUMP PLUG TO 1500 PSI. WAIT 2 MINS. RELEASE PRESSURE. FLOAT HEID. GOOD CEMENT RETURNS TO SURFACE = 11 BBL SLURRY TO PIT. JOB COMPLETE. RIG DOWN.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 201	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	125 SKS	50/50 Pozmix Cement	11.25	1406.25
C 206	630 #	Gel 6%	.20 #	126.00
C 208	125 #	PhenoSeal 1"/SK	1.25 #	156.25
C 202	75 SKS	OWC Cement	19.15	1436.25
C 208	75 #	PhenoSeal 1"/SK	1.25 #	93.75
C 206	500 #	Gel Flush	.20 #	100.00
C 214	40 #	Hulls	.45 #	18.00
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
C 108 A	9.38 TONS	Ton Mileage BULK TRUCKS x 2	M/C x 2	690.00
C 113	3 HRS	100 BBL VAC TRUCK	85.00	255.00
C 224	3,500 GALS	CITY WATER	10.00/1000	35.00
<u>THANK YOU</u> <u>AA</u>			Sub Total	5530.00
			Less 5%	291.02
			8.5% Sales Tax	290.41
				5529.39

Authorization Called By Joel Title \_\_\_\_\_ Total 5529.39

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.