

1602 - 9:00

SM Oil & Gas, Inc.
P. O. Box 189
Skiatook, Oklahoma 74070
620-725-3200

June 1, 2017

Kansas Corporation Commission
Conservation Division
266 N. Main Street – Suite #220
Wichita, Kansas 67202-1513


Re: Goode "A" 7-2
API #15-019-27579-00-00
Cement Usage ACO-1

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 12 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast
Area Manager

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report

Ticket No. **3359**
 Foreman Russell McCoy
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-6-17	1180	Goode "A" 7-2				CQ	KS
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
S.M. Oil + Gas	P.O. Box 189	SK: took	OK		8M AM 200 JASIN	104 114 112	ALAN M Zevi JASON

Job Type Longstring Hole Depth 1615 Slurry Vol. 36 Lead 20 Tail Tubing _____
 Casing Depth 1602 Hole Size 6 3/4 Slurry Wt. 12.8 14" Drill Pipe _____
 Casing Size & Wt. 4 1/2 11.60 Cement Left in Casing 0 Water Gal/SK _____ Other _____
 Displacement 25 Displacement PSI 900 Bump Plug to 1450 BPM 5

Remarks: Safety meeting, Rig to 4 1/2 casing, Break circulation w/ 38 Bbl water
Mix + Pump 500# Gel w/ Hull's Pump 5 Bbl Fresh water spacer. Mix 125
SK's light cement w/ 6% Gel 1# Phenoseal @ 12.8 = 35 Bbl Slurry Tail w/ 75
SK's owc w/ 1# Phenoseal @ 14" = 20 Bbl Slurry, wash out Pump + Lines
Release 4 1/2 Top Rubber Plug Displace w/ 25 Bbl city water. Final Pump
PSI 900# Bump Plug to 1400-1450# check float float held. 10 Bbl cement
Slurry to surface. Annulus stayed full of cement. Job complete, Tear Down.
Close casing in @ 0 PSI. Thank you
Russell McCoy

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge	1050.00	1050.00
C-107	30	Mileage	3.95	118.50
C-204	125	SK's 50/50 Premix	11.25	1406.25
C-206	630#	Gel = 6%	.20	126.00
C-208	125#	Phenoseal 1# per/sk	1.25	156.25
C-202	75	SK's owc cement	19.15	1436.25
C-208	75#	Phenoseal 1# per/sk	1.25	93.75
C-206	500#	Gel Flush	.20	100.00
C-214	40#	Hull's	.45	18.00
C-108A		Tow mileage Bulk Truck x 2	345	690.00
C-403	1	4 1/2 Top Rubber Plug	45.00	45.00
C-113	2 1/2 hr	100 Bbl VAC Truck	85.00	212.50
C-224	3,500	Gallow's city water	10 per/1000	35.00
			SubTOTAL	5,487.50
			590	5,877.50
			Sales Tax	290.40
				6,167.90

Authorization by JOEL Potts Title co/owner Total 6,167.90

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.