

**SM Oil & Gas, Inc.**  
**P. O. Box 189**  
**Skiatook, Oklahoma 74070**  
620-725-3200

May 26, 2017

*Kansas Corporation Commission  
Conservation Division  
266 N. Main Street – Suite #220  
Wichita, Kansas 67202-1513*


**Re: Goode "A" 9-2  
API #15-019-27569-00-00  
Cement Usage ACO-1**

To Whom It May Concern:

*SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 12 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.*

*An invoice showing the bulk quantity of cement is available if needed.*

Thank you,



Thomas H. Oast  
Area Manager

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **3354**  
 Foreman Russell McLOY  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-1-17	1180	Gudd A9-2				CO	KS
Customer S.M. Oil + Gas INC.			Safety Meeting Rm JAS AB 2ev.	Unit # 104 114 113	Driver AB 2ev. JASON	Unit #	Driver
Mailing Address P.O. Box 189			City SKIA TOOK	State OK	Zip Code 74070		

Job Type Longstring Hole Depth 1615 Slurry Vol. 34 LEAD 20 TAIL Tubing \_\_\_\_\_  
 Casing Depth 1604 Hole Size 6 3/4 Slurry Wt. 12.8 14 Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 1160 Cement Left in Casing 0 Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 25 Bbl Displacement PSI 900 Bump Plug to 1400 BPM 4

Remarks: Safety Meeting, Rig to 4 1/2 casing, Break Circulation w/ 51 Bbl water, mix + Pump 500# Gel w/ Hulls, Pump 5 Bbl water spacer mix 12.5 SK's light wt cement w/ 6% Gel 1# Phenoseal @ 12.8 = 34 Slurry, TAIL w/ 75 SK's owc cement w/ 1# Phenoseal @ 14 = 20 Bbl Slurry, wash out Pump + Lines, Release 4 1/2 TOP Rubber Plug. Displace w/ 25 Bbl city water. Final Pump PSI 900# Bump Plug to 1400# check FLOAT, FLOAT HEAD. 12 Bbl Slurry to Pit. Annulus stayed Full. Job complete, TANK DOWN.

THANK YOU  
 Russ + crew

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge	1050.00	1050.00
C-107	30	Mileage	3.95	118.50
C-204	125	SK's 50/50 Pozmix cement	11.25	1406.25
C-206	630 #	Gel = 6%	.20	126.00
C-208	125 #	Phenoseal 1# Per/SK	1.25	156.25
C-202	75	SK's owc cement	19.15	1436.25
C-208	75 #	Phenoseal 1# Per/SK	1.25	93.75
C-206	500 #	Gel Flush	.20	100.00
C-214	40 #	Hulls	.45	18.00
C-403	1	Top Rubber Plug	45.00	45.00
C-108A	1	Tow mileage BULK TRUCK x 2	m/c 345.00	690.00
C-113	2 1/2 hr	100 Bbl VAC TRUCK	85.00	212.50
C-224	3,500	gallons city water	10 Pr/1,000	35.00
<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block;">           6% @ 288.90            \$ 5489.01         </div>			Sub TOTAL	5,487.50
			Sales Tax	290.41
Authorization by <u>JOEL BETTS</u> Title <u>CO/OWNER</u>			Total	<u>5777.91</u>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.