



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

100424
 40622

TICKET NUMBER 56104
 LOCATION Oakley ks
 FOREMAN Cory Davis

FIELD TICKET & TREATMENT REPORT
 CEMENT

Invoice #900156

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-18-19	2777	Rohleder #1	7	85	26 W	Graham
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Culbreath oil & gas Co, Inc			731	Neil White		
MAILING ADDRESS			70	Matadi Jnrub - Xavier Colby		
3501 South Yale Avenue			703	Cory Davis - Kaleb Copton		
CITY	STATE	ZIP CODE	1098	Walt Dinkel		
Tulsa	OK	74135				

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 263 CASING SIZE & WEIGHT 85/8 23 #
 CASING DEPTH 263 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 15.2 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 15'-20'
 DISPLACEMENT 15.5 DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 BPM

REMARKS: Safety meeting, rig up on STP Dwg, circ casing on bottom
mix 185 SKS com, 3% cc - 2% gel, Displace 15.5 BBL H2O, Shut in

Walt + Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
Co0451	1	PUMP CHARGE	1,150.00	1,150.00
Co0002	30	MILEAGE	7.15	214.50
Co0711	8.70		1.75	660.00
CC 5871	18.5 SKS	Surface Blend II	24.00	4,440.00
				6,464.50
				Less 2.5% Disc - 1,616.13
				4,848.37
				SALES TAX 249.76
				ESTIMATED TOTAL 5098.13

AVIN 3737
 AUTHORIZATION Walt Dinkel TITLE Foreman DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

100454
410652

TICKET NUMBER 55994

LOCATION Oakley Ks

FOREMAN Cory Davis

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice # 900788

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
7-24-19	2777	Rohleder #1	7	8 ^s	26W	Graham	
CUSTOMER Culbreath oil & Gas inc			Horse ks STEAD 406				
MAILING ADDRESS 3501 South Yale Avenue			13 West to R110 IN 1/4 W 1/4				
CITY Tulsa		STATE OK	ZIP CODE 74135				
TRUCK #		DRIVER		TRUCK #		DRIVER	
753		Cory D					
566		Kaleb C					
703		Xavier C					

JOB TYPE PTA HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT _____
 CASING DEPTH _____ DRILL PIPE 4 1/2 TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting rig up on STD Drilling circ. mud plug as ordered @ 2345'
 #1 Pump 5 BBL H2O ahead mix 8 BBL cement / 50 sks wash up with 5 BBL water Pump 2 min mud
 #2 @ 1450' mix 16 BBL cement / 100 sks Displace 5 BBL water
 #3 @ 325' mix 8 BBL cement / 50 sks Displace 2 BBL H2O
 #4 @ 40' Push 8 5/8 Plug down mix 2 BBL cement / 15 sks
 R.H. mix 4 BBL cement wash up & Rig down

Thanks Cory & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0451	1	PUMP CHARGE	1900 ⁰⁰	1900 ⁰⁰
CE0002	30	MILEAGE	7 ¹⁵	214 ⁵⁰
CE0711	10.32	Ton mileage Delivery min	1 ⁷⁵	660 ⁰⁰
CC5829	240 sks	Lite-Weight Blend	16 ⁰⁰	3,840 ⁰⁰
CP8228	1	8 5/8 wooden Plug	165 ⁰⁰	165 ⁰⁰
			sub total	6,779.50
			25% Dis	1694.88
			sub total	5084.62
			SALES TAX	225.28
			ESTIMATED TOTAL	5309.91

AVIN 3737 *[Signature]* *[Signature]* AUTHORIZATION _____ TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form