



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61  
P.O. Box 8613  
Pratt, Kansas 67124  
Phone 620-672-1201

FIELD SERVICE TICKET  
1718 17637 A

DATE \_\_\_\_\_ TICKET NO. \_\_\_\_\_

DATE OF JOB <b>2-10-19</b> DISTRICT <b>Pratt</b>		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:						
CUSTOMER <b>LD Drilling inc</b>		LEASE <b>McIntyre</b> WELL NO. <b>1-20</b>						
ADDRESS		COUNTY <b>Rush</b> STATE <b>KS</b>						
CITY STATE		SERVICE CREW <b>MATTAI Marquez Dominguez SCOTT</b>						
AUTHORIZED BY		JOB TYPE: <b>2-42 5 1/2" Long string</b>						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	TIME
<b>20920</b>	<b>1</b>						<b>2-10</b>	<b>2:45</b>
						ARRIVED AT JOB		<b>8:40</b>
<b>19918</b>	<b>.5</b>					START OPERATION		<b>8:39</b>
						FINISH OPERATION		<b>9:30</b>
						RELEASED		<b>10:30</b>
						MILES FROM STATION TO WELL		<b>65</b>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: *X RRL WLR*  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP 105	AA-2 cmt	SK	150		2,550.00
CP 103	60/40 P02	SK	30		360.00
CC 102	Colliflax	lb	38		1,400.00
CC 105	C-41 P	lb	71		284.00
CC 111	SAT	lb	814		407.00
CC 113	Gypsum	lb	705		528.75
CC 148	C-17	lb	92		1,840.00
CC 200	cmt gel	lb	52		13.00
CC 201	Gilsonite	lb	898		601.66
CR 125	Auto fill float shut 5 1/2	ea	1		360.00
CR 607	Latch down plug + basket 5 1/2	ea	1		400.00
CR 190	basket 5 1/2	ea	1		290.00
CR 165	turbulizer 5 1/2	ea	8		680.00
E 100	P.U. miles	Mi	65		292.50
E 101	heavy eq miles	Mi	130		975.00
E 113	prop + bulk del	TM	543		1,356.84
CR 204	depth chaser 3001-4000'	4hr	1		2,160.00
CC 240	blend + mix	SK	180		252.00
	plug container	job	1		250.00
S 003	supervisor	ea	1		
CC 151	CHEMICAL / ACID DATA: <b>muo flusy</b>	gal	1,000		
				SB TOTAL	15,616.39

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		<b>9,369.83</b>

SERVICE REPRESENTATIVE <b>Mike Mattai</b>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY <i>X RRL WLR</i>
---	---

FIELD SERVICE ORDER NO. \_\_\_\_\_ (WELL OWNER OPERATOR CONTRACTOR OR AGENT)

Customer LD Drilling inc	Lease No.	Date 2-10-19
Lease McIntyre	Well # 1-20	
Field Order # 17637	Station Pratt	Casing 5 1/2
		Depth 3205
Type Job 2-42 5 1/2" Long String	Formation	County Rush
		State KS
		Legal Description 20-18S-16W

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME	
Casing Size 5 1/2	Tubing Size	Shots/Ft		Acid 150 SXS AA-2	RATE 2 1/2 bbl/min	PRESS 490 psi	ISIP
Depth 3700	Depth	From	To	Pre Pad 35 SXS AA-2	Max 4040 PSI	490 psi	5 Min.
Volume 88.1	Volume	From	To	Pad	Min		10 Min.
Max Press 1,500	Max Press	From	To	Frac	Avg		15 Min.
Well Connection PC	Annulus Vol.	From	To		HHP Used		Annulus Pressure
Plug Depth 3084	Packer Depth	From	To	Flush 87.6	Gas Volume		Total Load

Customer Representative Rick Wilson	Station Manager Westerman	Treater MATTAL
Service Units 83353	84980	20920
Driver Names MATTAL	Marquez	Domingo
		19960
		19918

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
6:40					ON LOCATION
					16' shoe JT 15.5# csng (used)
					Turbos 1,3,5,7,9,11,13,15 BASKET 2
7:30					CSNG ON BOTTOM
7:38					HOOK TO CSNG/BREAK CIRC W. RIG
8:39	300		5	5.5	PUMP 5 bbl WATER
8:41	300		24	5.5	PUMP 24 bbl mud flush
8:44	300		5	5.5	PUMP 5 bbl WATER
8:47	400		41	5	MIX 150 SXS AA-2
8:55			4	4	WASH PUMP+LINE/DROP PLUG
8:57	200		-	6.5	START DISPLACEMENT
9:10	300		67	6.5	LIFT PRESSURE
9:12	400		77	3	SLOW RATE
9:15	1500		87.6	-	PLUG DOWN, RELEASED + HELD
9:20			7		PLUG RAT HOLD
					CIRCULATION THRU JOB
					JOB COMPLETE
					THANK YOU!
					MIKE MATTAL
					SCOTTY, EDMOND, DOMINGO