

TTM B: 75

FIELD SERVICE TICKET

1718 17478 A

0041144159



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

34-33s-8w

DATE _____ TICKET NO. _____

DATE OF JOB <u>11/11/2018</u> DISTRICT <u>Pratt, KS</u>		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:						
CUSTOMER <u>Stratton Exploration, LLC</u>		LEASE <u>Morrow</u> WELL NO. <u>2734</u>						
ADDRESS		COUNTY <u>Hesper</u> STATE <u>KS</u>						
CITY STATE		SERVICE CREW <u>Darin, Ed, David</u>						
AUTHORIZED BY		JOB TYPE: <u>2421958 surface</u>						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	TIME
<u>20920</u>	<u>1/2</u>						<u>11/10</u>	<u>4:00</u>
<u>19860</u>	<u>1/4</u>					ARRIVED AT JOB	<u>11/10</u>	<u>7:30</u>
						START OPERATION	<u>11/12</u>	<u>12:00</u>
						FINISH OPERATION	<u>11/12</u>	<u>12:30</u>
						RELEASED	<u>11/12</u>	<u>1:00</u>
						MILES FROM STATION TO WELL		<u>64</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: John [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
<u>CP1000</u>	<u>Common Cement</u>	<u>SK</u>	<u>250</u>		<u>4,000 00</u>
<u>CC109</u>	<u>Calcium Chloride</u>	<u>Lb</u>	<u>470</u>		<u>493 50</u>
<u>CE102</u>	<u>Cellulose</u>	<u>Lb</u>	<u>63</u>		<u>233 16</u>
<u>CF154</u>	<u>Wooden Cement Plug, 9 5/8</u>	<u>Eg</u>	<u>1</u>		<u>180 00</u>
<u>E100</u>	<u>Unit mileage charge - Pickup, Small US trucks</u>	<u>mi</u>	<u>60</u>		<u>270 00</u>
<u>E101</u>	<u>Heavy Equipment mileage</u>	<u>mi</u>	<u>120</u>		<u>900 00</u>
<u>E113</u>	<u>Proppant and Bulle Delivery Charge, per ton mile</u>	<u>ton</u>	<u>705</u>		<u>1,762 50</u>
<u>CE200</u>	<u>Depan Charge - 500</u>	<u>4hr</u>	<u>1</u>		<u>1,000 00</u>
<u>CE240</u>	<u>Blenders & mixing Service Charge</u>	<u>SK</u>	<u>250</u>		<u>350 00</u>
<u>CE504</u>	<u>Plug container Utilization Charge</u>	<u>Job</u>	<u>1</u>		<u>250 00</u>
<u>SO03</u>	<u>Service Supervisory First Shift on Loc.</u>	<u>Eg</u>	<u>1</u>		<u>175 00</u>
SUB TOTAL					<u>9,614 10</u>

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
DISCOUNT		
TOTAL		<u>3,768 46</u>

SERVICE REPRESENTATIVE Darin [Signature] THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY John [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



energy services, L.P.

TREATMENT REPORT

Customer Stratton Exploration, LLC	Lease No.	Date 11/11/2018
Lease Morrow	Well # 2734 H	
Field Order # 17478	Station Pratt, KS	Casing 9 5/8
Type Job 242/9 5/8 surface	Depth	County Harper
	Formation	State KS
		Legal Description 34-33s-8w

PIPE DATA		PERFORATING DATA		FLUID USED	TREATMENT RESUME		
Casing Size 9 5/8	Tubing Size	Shots/Ft		Acid	RATE	PRESS	ISIP
Depth 423	Depth	From	To	Pre Pad	Max		5 Min.
Volume 32.6	Volume	From	To	Pad	Min		10 Min.
Max Press 500	Max Press	From	To	Frac	Avg		15 Min.
Well Connection	Annulus Vol.	From	To		HHP Used		Annulus Pressure
Plug Depth 403	Packer Depth	From	To	Flush Water	Gas Volume		Total Load

Customer Representative	Station Manager Justin Waskimen	Treater Darin Franklin
Service Units 92911 84980 20920 19889 19860		
Driver Names Darin Ed Ed Devin Devin		

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
7:30pm					on location / safety meeting
					250 sk common cement, 2% calcium chloride, 1/4 H Cellofisker
					15.6 ppg, 1.20 yield, 5.23 water
12:00pm	200		3	5	Pump 3 bbls water
	200		53	5	mix 250 sk cement
					Shut down
					Release Plug
			0	5	Start displacement
			20	3	slow rate
12:30pm			29	3	Shut in
12:45pm					Job complete / Darin & crew
					Thank you!!!
					Reviewed 10 bbls cement

Cement Callsheet



Company	Stratakan Exploration, LLC		Service Point	Pratt, KS		620-672-1201	
			Contact Person	Justin Westerman			
Well Type	New	CONTRACTOR	WW #14	COUNTY	Harper	STATE	KS
LEASE	Morrow		WELL # 2734H	SEC	34	TWP	33s RANGE 08w

DIRECTIONS:

Attica, Kansas - 2 East to 80th, 7 1/2 South, East into

Job Type	425' Surface Casing		Casing Size	9 5/8	Thread	8rd	Weight
Equipment			Tubing/Drill Pipe Size		Thread		Weight
			Hole Size	12 1/4	Packer		Bridge Plug
Remarks:			Plug Container	Yes	Casing Swivel		Squeeze Manifold

9 5/8" Surface Casing

CEMENT DATA

LEAD 1	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
TAIL 1	Weight PPG	Type	Additives	
CP100C	15.60	Common Cement	2% calcium chloride 0.25 pps celloflake	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
250	125%	1.20	5.23	
LEAD 2	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
TAIL 2	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
Rat Hole	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	

Float Equipment

Part #	Quantity	Description	# Used	# Returned
CF154	1	Wooden Cement plug, 9 5/8"		

Misc. Chemicals

Ordered By	Phone	Fax	Date of Job	11/10/18
Call Taken By	Kevin Brungardt	Phone 620-213-1586	Email	Time Ready
Operator or Driver Called	Josh/Toolpusher cell: 918-839-0425		Call Out Time	W/C