

JSM 101 100

FIELD SERVICE TICKET  
1718 17538 A  
0041146642



10244 NE Hwy. 61  
P.O. Box 8613  
Pratt, Kansas 67124  
Phone 620-672-1201

DATE \_\_\_\_\_ TICKET NO. \_\_\_\_\_

DATE OF JOB: 11-21-16	DISTRICT: Pratt Kansas	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:	
CUSTOMER: Stratokam Exploration LLC	LEASE: Morrow 2734H	WELL NO.:						
ADDRESS:	COUNTY: Harper	STATE: Kansas						
CITY:	STATE:	SERVICE CREW: Fennis, Mike, David, Derrin						
AUTHORIZED BY:	JOB TYPE: 7" Intermediate casing 2-42							
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	TIME
46779	1 1/4						11-20-16	1430
19860	1/2					ARRIVED AT JOB	11/20	1400
						START OPERATION	11/20	9:45
						FINISH OPERATION	11/21	11:00
						RELEASED	11/21	11:30
						MILES FROM STATION TO WELL		60

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).  
The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: John Green  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP100P	Premium cement	SK	200		3,600 00
CC111	salt	lb	1005		502 50
CC112	Cement Friction Reducer	lb	57		342 00
CC113	Gypsum	lb	940		705 00
CC148	C-17	lb	94		1,580 00
CC201	Gilsonite	lb	1001		670 67
CC105	C-410	lb	94		376 00
CF252	7" Regular guide shoe (Blues)	EA	1		300 00
CF952	7" Float collar (Blues)	EA	1		400 00
CF104	7" Top Rubber cement Plug	EA	1		110 00
CF1653	7" straight vane turbolator w/set screw 7" x 4 3/4"	EA	10		4,000 00
CF151	Mud Flush	Gal	500		750 00
E100	Pickup mileage	Mi	60		270 00
E101	Heavy equipment mileage	Mi	120		900 00
E113	Bulk delivery charge per ton mile	Ton/Mi	564		1,410 00
CF206	Depth charge 500' - 600'	1/HR	1		2,880 00
CF240	Blending & mixing service charge	SK	200		280 00
CF504	Plug container utilization charge	5b	1		250 00
5003	Service supervisor first 8 hrs on location	EA	1		175 00
SUB TOTAL					19,801 10

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		11,580

SERVICE REPRESENTATIVE: David Fulmer  
THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: John Green  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO. \_\_\_\_\_

Customer <b>Stratokan Exploration</b>	Lease No.	Date <b>November 21, 2014</b>
Well # <b>27341H</b>	Well # <b>27341H</b>	
Field Order # <b>17536</b>	Station <b>Proff Kansas 1716</b>	Casing <b>7"</b>
Type Job <b>7" Intermediate 2-42</b>	Depth <b>5164</b>	County <b>Harper</b>
	Formation <b>TD-5150</b>	State <b>KS</b>
		Legal Description <b>34-333-08W</b>

PIPE DATA		PERFORATING DATA		FLUID USED	TREATMENT RESUME		
Casing Size	Tubing Size	Shots/Ft		Acid	RATE	PRESS	ISIP
<b>7"</b>							
Depth <b>5164</b>	Depth	From	To	Pre Pad	Max		5 Min.
Volume <b>197</b>	Volume	From	To	Pad	Min		10 Min.
Max Press	Max Press	From	To	Frac	Avg		15 Min.
Well Connection <b>2 1/2"</b>	Annulus Vol.	From	To		HHP Used		Annulus Pressure
Plug Depth <b>5120</b>	Packer Depth	From	To	Flush <b>Water</b>	Gas Volume		Total Load

Customer Representative <b>Josh</b>	Station Manager <b>Susan Westerman</b>	Treater <b>Femis Ladwin</b>
Service Units <b>78668</b>	<b>71686</b>	<b>86779</b>
Driver Names <b>Femis</b>	<b>Mike</b>	<b>Mike</b>
	<b>Psrin</b>	

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<b>1400</b>					<b>Arrived on Location / Safety meeting</b>
<b>1630</b>					<b>Rig up equipment</b>
					<b>200SK Premium Cement, 5% gypsum</b>
					<b>0.5% defoamer, 10% SS12, 0.3% Arision</b>
					<b>reducer, 0.5% Fluiz loss, Spps Silsonit</b>
					<b>15.0 pps, 1.44 veils, 6.03 water</b>
<b>9:45pm</b>	<b>400</b>		<b>3</b>	<b>6</b>	<b>Pump 3 bbls water</b>
	<b>400</b>		<b>12</b>	<b>6</b>	<b>Pump 12 bbls Flush</b>
	<b>400</b>		<b>3</b>	<b>6</b>	<b>Pump 3 bbls water</b>
	<b>400</b>		<b>51</b>	<b>6</b>	<b>mix 200SK cement</b>
					<b>Shut down</b>
					<b>Wash pump &amp; line &amp; Release Plug</b>
	<b>250</b>		<b>0</b>	<b>7</b>	<b>Start displacement</b>
	<b>500</b>		<b>145</b>	<b>7</b>	<b>Lift Pressure</b>
	<b>2300</b>		<b>160</b>	<b>3</b>	<b>Slow Rise - Hole Peckings OK</b>
<b>11:00pm</b>	<b>3000</b>		<b>192</b>	<b>3</b>	<b>Bump Plug</b>
					<b>Plug - Set</b>
<b>11:30pm</b>					<b>Job Complete / Psrin screw</b>
					<b>Thsn &amp; Veil</b>

# Cement Callsheet



Company	Stratakan Exploration, LLC			Service Point	Pratt, KS		
				Contact Person	Justin Westerman 620-672-1201		
Well Type	New	CONTRACTOR	WW #14	COUNTY	Harper	STATE	KS
LEASE	Morrow		WELL # 2734H	SEC	34	TWP	33s RANGE 08W

**DIRECTIONS:**

Attica, Kansas - 2 East to 80th, 7 1/2 South, East into

Job Type	5100' Production Casing			Casing Size	7	Thread	8rd	Weight
Equipment				Tubing/Drill Pipe Size		Thread		Weight
				Hole Size	8 3/4	Packer		Bridge Plug
Remarks:	Pick up our 9 5/8" head & manifold			Plug Container	Yes	Casing Swivel		Squeeze Manifold

## 7.0" Production Casing

### CEMENT DATA

LEAD 1	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
TAIL 1	Weight PPG	Type	Additives	
CP100P	15.00	Premium Cement	5% gypsum + 0.5% defoamer 10% salt + 0.3% friction reducer 0.5% fluid loss + 5 pps gilsonite	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
200	35%	1.44	6.03	
LEAD 2	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
TAIL 2	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	
Rat Hole	Weight PPG	Type	Additives	
Sacks	Excess	Yield Ft/sk	Water Gal/sk	

### Float Equipment

Part #	Quantity	Description	# Used	# Returned
CF252	1	Guide Shoe - Regular, 7" (Blue)		
CF952	1	7" Float Collar (Blue)		
CF104	1	Top Rubber Cement Plug, 7" <i>in head</i>		
CF1653	10	Straight Vain Turbolator w/set Screw, 7" x 8 3/4"		
		<i>Head/manifold</i>		

### Misc. Chemicals

CC151	500	Mud Flush		
-------	-----	-----------	--	--

Ordered By	Phone	Fax	Date of Job	11/20/18
Call Taken By	Kevin Brungardt	Phone 620-213-1586	Email	Time Ready
Operator or Driver Called	Josh/Toolpusher cell: 918-839-0425			Call Out Time