

MAY 09 2019

mf



PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1000335	1718	05/06/2019
INVOICE NUMBER			
92964971			

Pratt (620) 672-1201
 B BEREKCO LLC
 I 2020 N BRAMBLEWOOD
 L WICHITA
 L KS US 67206
 T
 O ATTN: VICKEY LOVETTE

J LEASE NAME KYSAR 1-19
 O LOCATION
 B COUNTY KEARNY
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41173689	19572		Net - 30 days	06/05/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 05/04/2019 to 05/04/2019</i>				
0041173689				
1718195021 Cement-New Well Casing/Pi 05/04/2019 CEMENT SURFACE CASING				
A-Serv Lite	750.00	SK	7.41	5,557.50 T
150 SKS Premium Cement	1.00	SK	1,393.50	1,393.50 T
2241 LBS Calcium Chloride	1.00	LB	1,344.60	1,344.60 T
226 LBS Celluloflake	1.00	LB	476.86	476.86 T
Guide Shoe - Regular, 8 5/8" (Blue)	1.00	EA	224.20	224.20
Flapper Type Insert Float Valves. 8 5/8"	1.00	EA	165.20	165.20
Top Rubber Cement Plug, 8 5/8"	1.00	EA	132.75	132.75
Centralizer, 8 5/8" (Blue)	3.00	EA	53.10	159.30
240 Heavy Equipment Mileage	1.00	MI	1,027.20	1,027.20
Blending & Mixing Service Charge	1.00	SK	720.00	720.00
Proppant and Bulk Delivery Charges	1.00	MI	3,406.26	3,406.26
Depth Charge, 1001'-2000'	1.00	HR	855.00	855.00
Plug Container Utilization Charge	1.00	EA	142.50	142.50
50 Light Vehicle Mileage	1.00	MI	154.20	154.20
Cement Data Acquisition Monitor Strip	1.00	EA	313.50	313.50
Service Supervisor Charge	1.00	EA	75.00	75.00
Driver Charge	4.00	EA	35.00	140.00

BCP

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	16,287.57
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	570.21
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	16,857.78
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



PRESSURE PUMPING

Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

Job Log

Customer:	Berexco, LLC	Cement Pump No.:	37223 19572 19HRS	Operator TRK No.:	94245
Address:	2020 N Bramblewood	Ticket #:	1718 19502 L	Bulk TRK No.:	30463 19578 30464 37547
City, State, Zip:	Wichita Ks 67206	Job Type:	Z-42 Cement Surface Casing		
Service District:	1718-Liberal Ks	Well Type:	OIL		
Well Name and No.:	Kysar # 1-19	Well Location:	19-21S-35W	County:	Kearny
				State:	Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
A-Serv Lite	750	6%Gel, 3%Calcium Chloride, 1/4 pps Cello-flake	30463 19578	30464 37547	Front Back
Premium Plus Cement	150	2%Calcium Chloride, 1/4pps Cello-flake	27808 19883		Front Back
					Front Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	12.3	2.08	11.52	1560	TT Man Hours:	98
Tail:	14.8	1.35	6.35	202.5	# of Men on Job:	5

Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
20:30pm							Arrived at location
20:45pm							Spot trucks/Rig up
5:15am							Safety meeting
6:25am						1500	Pressure test lines to 1500psi
6:26am	6	10				200	Pump 10bbls of fresh water spacer
6:28am	6	277				210	Pump 277bbbs of lead cement from 750sks @12.3#
7:11am	6	36				290	Pump 36bbbs of tail cement from 150sks @14.8#
7:20am							Shut down/drop plug/Wash pump and lines
7:23am							Start displacement of 122bbbs with fresh water
7:27am	6	20				250	20bbbs gone
7:30am	6	40				310	40bbbs gone
7:34am	6	60				400	60bbbs gone
7:38am	6	80				550	80bbbs gone
7:41am	6	100				680	100bbbs gone
7:43am	6	110				700	110bbbs gone/slow down rate
7:45am	3	122				1050	Bump plug
							Check if float holds
							Got 50bbbs of cement to surface
							Rig down
							Job completed
							Thanked company man

Size Hole	12 1/4	Depth	1960		TYPE	Float Collar	
Size & Wt. Csg.	8 5/8 24#	Depth	1959	New / Used	Float	1915.8	Depth
Landing PSI	500+	Depth			Retainer		Depth
Shoe Joint	43.2	Type			Perfs		CIBP

Customer Signature: <i>Walter Brown</i>	Basic Representative:	Victor A. Corona
	Basic Signature:	<i>Victor A. Corona</i>
	Date of Service:	5/4/2019

Berexco LLC
8 5/8 Surface
Kysar 1-19
5/4/2019

