



RJ Energy

22082 NE Neosho Rd Garnett, Kansas 66032

Murray Twins 9-A

			Start	3-5-19
			Finish	3-7-19
9	soil	9		
24	clay/gravel	33		
54	shale	87		
80	lime	167		
101	shale	268		
111	lime	379		
57	shale	436		
65	lime	501	Set 40' of 7" w/5sxs	
8	shale	509	Ran 996' of 2 7/8	
50	lime	559	cemented to surface 125sxs	
186	shale	745		
24	lime	769		
50	shale	819		
29	lime	848		
13	shale	861		
10	lime	871		
15	shale	886		
8	lime	894		
8	shale	902		
6	lime	908		
28	shale	936		
6	Sandy shale	942	Odor	
3	bkn sand	945	Show	
8	bkn sand	953	Good show	
49	shale	1002	T.D.	