



RJ Energy

22082 NE Neosho Rd Garnett, Kansas 66032

Murray Twins 7-1

			Start 3-7-19
			Finish 3-11-19
9	soil	9	
20	clay/gravel	29	
58	shale	87	
84	lime	171	
98	shale	269	
109	lime	378	
52	shale	430	
72	lime	502	Set 40' of 7" w/5sxs
9	shale	511	Ran 987.3' of 2 7/8
48	lime	559	cemented to surface 125sxs
185	shale	744	
24	lime	768	
46	shale	814	
35	lime	849	
15	shale	864	
8	lime	872	
14	shale	886	
8	lime	894	
6	shale	900	
6	lime	906	
30	shale	936	
6	Sandy shale	942	Odor
3	bkn sand	945	Show
7	bkn sand	952	Good show
39	shale	991	T.D.