



RJ Energy

22082 NE Neosho Rd Garnett, Kansas 66032

Murray Twins 11-I

			Start 3-21-19
			Finish 3-25-19
9	soil	9	
22	clay/gravel	31	
57	shale	88	
83	lime	171	
99	shale	270	
110	lime	380	
46	shale	426	
74	lime	500	Set 40' of 7" w/5sxs
6	shale	506	Ran 967' of 2 7/8
52	lime	558	cemented to surface 125sxs
184	shale	742	
26	lime	768	
49	shale	817	
30	lime	847	
15	shale	862	
8	lime	870	
9	shale	879	
13	lime	892	
8	shale	900	
4	lime	904	
32	shale	936	
7	Sandy shale	943	Odor
10	bkn sand	953	Good show
20	shale	973	T.D.