

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
4559
 Ticket No. _____
 Foreman Russell McCoy
 Camp Eureka

API 15-073-21017-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
6-13-19	1,000	Gilroy # 21	6	25	13	G.W.	Ks	
Customer <u>Trimble + MacLuskey Oil LLC</u>			Safety Meeting Rm. zevi AB Steve		Unit #	Driver	Unit #	Driver
Mailing Address <u>P.O. Box 171</u>					102	zevi		
City <u>Girdley</u>					110	AB		
State <u>Ks</u>					145	Steve		
Zip Code <u>66852</u>								

Job Type P.T.A. old well Hole Depth N.A. Slurry Vol. 26 Bbl Tubing 2 3/8 1/2"
 Casing Depth 1639 Hole Size N.A. Slurry Wt. 13.5 Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK 6 Other _____
 Displacement - Displacement PSI _____ Bump Plug to _____ BPM 3

Remarks: Safety meeting + Job Procedure

15 SKs @ 1419'
 15 SKs @ 600'
 70 SKs @ 250' (30 SKs @ 250' Inside 4 1/2
 40 SKs 157' to Surface on Annulus)

NOTE'S WASH Down on Annulus of 4 1/2 w/ 1/2 PIPE SOLID @ 157'
 CALL Harry w/ KCC OK to Plug @ 157' on Annulus 250' to Surface on Inside of 4 1/2
 Gel Spacers Between Plugs

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	785.00	785.00
C-107	20	Mileage	4.20	84.00
C-203	100	SKs 60/40 P2mix	13.40	1340.00
C-206	350 #	Gel = 4%	.21	73.50
C-206	250 #	Gel For Gel Spacer	.21	52.50
C-214	45 #	cottonseed hulls mixed w/ cement	.50	22.50
C-108	4.3 Ton	Ton Mileage on Bulk Trk	n/c	365.00
C-113	4	hr 80 Bbl UAC Truck	90.00	360.00
C-224	3,000	gallons city water	10.00 per 1000	30.00
	160'	1/2 wash PIPE Rental w/ Wash Head	N.C.	N.C.
			590	3,112.50
		Sales Tax		< 168.00 > 249.00
Authorization	by Brian MacLuskey Title Col Rep		Total	3193.42

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.