

McGOWAN

DRILLING, INC.

Mound City, KS

620.224.7406

Well #				Casing			
Dennis Crotts #7-I				Surface		Longstring	
RJ ENERGY, LLC				Size:	7.0 "	Size:	2 7/8 "
				Tally:	42 '	Tally:	1035.75 '
API #:	1503124386	S-T-R:	28-22-16E	Cement:	5 sx	Bit:	5.875 "
County:	Coffey	Date:	4/5/2019	Bit:	9.875 "	Date:	4/10/2019
Top	Base	Formation	Top	Base	Formation		
0	2	Soil					
2	18	Clay					
18	25	Sand & gravel					
25	203	Shale					
203	247	Lime					
247	335	Shale					
335	360	Lime					
360	371	Shale					
371	381	Lime					
381	390	Shale					
390	461	Lime					
461	476	Shale					
476	479	Lime					
479	513	Shale					
513	576	Lime					
576	586	Shale					
586	603	Lime					
603	609	Shale					
609	612	Lime					
612	617	Shale					
617	627	Lime					
627	818	Shale					
818	826	Lime					
826	833	Shale					
833	838	Lime					
838	886	Shale					
886	891	Lime					
891	912	Shale					
912	915	Lime					
915	930	Shale					
930	935	Lime					
935	955	Shale					
955	957	Lime					
957	966	Shale					
966	968	Lime					
968	1003	Shale					
1003	1018	Sand					
1018	1038	Shale	Total Depth:		1038		

Sand / Core Detail		
Core #1:	Core #2:	
1003	1006	Laminated sand, slight bleed to pit, good odor.
1006	1009	Good odor, great bleed to pit, laminated.
1009	1014	Good odor, soft, excellent bleed to pit.
1014	1018	Sandy shale, slight bleed in samples.