



RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

Ingwerson 1IR

			Start 6-20-19
			Finish 6-25-19
4	soil	4	
35	clay/gravel	139	
107	shale	246	
43	lime	289	
18	shale	307	
51	lime	358	
62	shale	420	
94	lime	514	Set 40' of 7" w/5sxs
14	shale	528	Ran 1062.1 of 2 7/8
10	lime	538	cemented to surface 135sxs
21	shale	559	
106	lime	665	
169	shale	834	
29	lime	863	
57	shale	920	
31	lime	951	
15	shale	966	
8	lime	974	
14	shale	988	
5	lime	993	
6	shale	999	
5	lime	1004	
33	shale	1037	
4	sandy shale	1041	odor
7	bkn sand	1048	Good Show
20	Shale	1068	T.D.