

SM Oil & Gas, Inc.
P. O. Box 189
Skiatook, Oklahoma 74070
620-725-3200

June 28, 2017

Kansas Corporation Commission
Conservation Division
266 N. Main Street – Suite #220
Wichita, Kansas 67202-1513


Re: McCall #10
API #15-019-27585-00-00
Cement Usage ACO-1

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,

A handwritten signature in black ink, appearing to read 'TH Oast', is written over the printed name.

Thomas H. Oast
Area Manager

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report

Ticket No. 3394
 Foreman Kevin McCoy
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
6-30-17	1180	McCALL # 10				CQ	Ks	
Customer	Mailing Address	City	State	Zip Code	Unit #	Driver	Unit #	Driver
S. M. OIL & GAS	P.O. Box 189	SKIATOOK	OK	74070	105	DAVE G.		
					110	JASON H.		
					113	Steve m.		
					141	RICK L.		

Job Type Longstring Hole Depth 1620' Slurry Vol. 34 BBL Lead 20 BBL Tail Tubing _____
 Casing Depth 1606' Hole Size 6 3/4" Slurry Wt. 12.8-14* Drill Pipe _____
 Casing Size & Wt. 4 1/2 11.60* Cement Left in Casing 0' Water Gal/SK _____ Other _____
 Displacement 25.5 BBL Displacement PSI 950 Bump Plug to 1450 PSI BPM _____

Remarks: Safety Meeting: Rig up to 4 1/2 casing. Break circulation w/ 40 BBL fresh water. Pump 500# Gel Flush w/ Halls, 5 BBL water spacer. Mixed 125 SKS 50/50 Pozmix Cement w/ 6% Gel, 1# PhenoSeal /SK @ 12.8*/gal = 34 BBL slurry, Tail in w/ 75 SKS OWC Cement w/ 1# PhenoSeal /SK @ 14*/gal = 20 BBL slurry. Wash out Pump & Lines, shut down. Release Plug. Displace Plug to seat w/ 25.5 BBL fresh water. Final Pumping Pressure 950 PSI. Bump Plug to 1450 PSI. Wait 2 mins. Release Pressure. Float Held. Shut in @ 0 PSI. Good Cement Returns to Surface = 12 BBL slurry to pt. Job Complete. Rig Down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	125 SKS	50/50 Pozmix Cement	11.25	1406.25
C 206	630 #	Gel 6% } Lead Cement	.20 #	126.00
C 208	125 #	PhenoSeal 1#/SK	1.25 #	156.25
C 202	75 SKS	OWC Cement } Tail Cement	19.15	1436.25
C 208	75 #	PhenoSeal 1#/SK	1.25 #	93.75
C 206	500 #	Gel Flush	.20 #	100.00
C 214	40 #	Halls	.45 #	18.00
C 108A	9.15 TONS	Ton Mileage	M/C x 2	690.00
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
C 113	3 HAS	80 BBL VAC TRUCK	85.00	255.00
C 224	3,300 GALS	CITY WATER	10.00/1000	33.00
			Sub Total	5528.00
			Less 5%	290.91
			Sales Tax	290.23
				5527.32

THANK YOU
 M

Authorization [Signature] Title _____ Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.