

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4473**
 Foreman Kevin M Coy
 Camp _____

API # 15-197-20307-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
5-8-19	1264	J. R. Ranch # 1	24	145	11E	WABAUNSEE	KS
Customer		Safety Meeting KM AM SM	Unit #	Driver	Unit #	Driver	
Mailing Address			104	ALAN M.			
City			112	STEVE M.			
State	Zip Code						
MT. VERNON	IL	62864-0546					

Job Type SURFACE Hole Depth 315' K.B. Slurry Vol. 43 BBL Tubing _____
 Casing Depth 313.41' K.B. Hole Size 12 1/4 Slurry Wt. 15.0 # Drill Pipe _____
 Casing Size & Wt. 8 5/8" 23 # Cement Left in Casing 20' Water Gal/SK 6.5 Other _____
 Displacement 18.7 BBL Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting: Rig up to 8 5/8 CASING. BREAK CIRCULATION w/ 10 BBL FRESH WATER. MIXED 180 SKS CLASS "A" CEMENT w/ 3% CaCl2, 2% GEL @ 15 #/GAL, yield 1.35 = 43 BBL SLURRY. Displace w/ 18.7 BBL FRESH WATER. Shut CASING IN. Good Cement RETURNS to SURFACE = 12 BBL SLURRY to PIT. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 101	1	Pump Charge	890.00	890.00
C 107	75	Mileage	4.20	315.00
C 200	180 SKS	CLASS "A" Cement	15.75	2835.00
C 205	500 #	CaCl2 3%	.63 #	315.00
C 206	340 #	GEL 2%	.21 #	71.40
C108 B	8.46 TONS	TON Mileage 75 miles	1.40	888.30
			Sub TOTAL	5314.70
			Less 5%	278.62
			SALES TAX 8%	257.71
Authorization <u>witnessed By Judd Gulick</u> Title <u>C & G Dely Tool pusher</u>			Total	5293.79

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.