

QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1334

Date	7-1-2019	Sec.	28	Twp.	11	Range	22	County	Trego	State	KANSAS	On Location		Finish	12:30AM
Lease								Location		Ogallah 5N (ADF) 13/4W 1/2N					
Beren's Reif								Well No.		#9					
Contractor								Owner		To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.					
PROFESSIONAL PULLING SERVICE															
Type Job								Charge To		CARTER ENERGY					
Plug ABANDONED well										15-195-21179-0000					
Hole Size								Street							
T.D.								City		State					
Csg. 4 1/2 CSG.								Depth		3980'					
Tbg. Size 2 3/8								Depth							
Tool 8 5/8								Depth		251					
Cement Left in Csg.								Shoe Joint		Cement Amount Ordered 275 sx 6940 4% GEL					
Meas Line								Displace		9 GEL 450# HULLS ON SIDE					
EQUIPMENT															
Pumptrk 20								No.		Cementer Helper					
Bulktrk 14								No.		Driver					
Bulktrk								No.		Driver					
								No.		Driver					
JOB SERVICES & REMARKS															
Remarks:								Used		Hulls 300# (6)					
Rat Hole										Salt					
Mouse Hole										Flowseal					
Centralizers										Kol-Seal					
Baskets										Mud CLR 48					
D/V or Port Collar										CFL-117 or CD110 CAF 38					
2 3/8 TUBING @ 3490'										Sand					
3490- SPOT 9 SX GEL - 50 SX CEMENT 100# HULLS										Handling 275					
1800- SPOT 100 SX CEMENT w/ 200# HULLS										Mileage					
900- CIRCULATE CEMENT TO SURFACE										FLOAT EQUIPMENT					
w/ 40 SX CEMENT. Pull- 2 3/8										Guide Shoe					
PUT ON 4 1/2 CSG. SWAGE & SQUEEZED										Centralizer					
IN ANOTHER 45 SX CEMENT										Baskets					
@ 300# & SHUT IN @ 300#.										AFU Inserts					
8 5/8 ANNULAS GOT IN APPROX										Float Shoe					
2 SX CEMENT @ 300# &										Latch Down					
SHUT IN @ 300#.										Pumptrk Charge plug					
fused 237 SX										Mileage 33					
9 9/16 300# HULLS															
THANKS!															
Signature															
												Tax			
												Discount			
												Total Charge			