

Elite Cementing & Acidizing of KS, LLC
 810 E 7th, PO Box 92
 Eureka, KS 67045



Date	Invoice #
3/11/2019	4344

Bill To	
D&J Investments PO Box 107 El Dorado, KS 67042	
Customer ID#	1242

Job Date	3/8/2019
Lease Information	
Seglem #4	
County	Butler
Foreman	DG

Item	Description	Qty	Terms	Net 15
			Rate	Amount
C101	Cement Pump-Surface	1	890.00	890.00
C107	Pump Truck Mileage (one way)	15	4.20	63.00
C200	Class A Cement-94# sack	125	15.75	1,968.75T
C205	Calcium Chloride	350	0.63	220.50T
C206	Gel Bentonite	235	0.21	49.35T
C108A	Ton Mileage (min. charge)	1	365.00	365.00

We appreciate your business!

Phone #	Fax #	E-mail
620-583-5561	620-583-5524	rene@elitecementing.com

Send payment to:
 Elite Cementing & Acidizing of KS, LLC
 PO Box 92
 Eureka, KS 67045

Subtotal	\$3,556.60
Sales Tax (6.5%)	\$145.51
Total	\$3,702.11
Payments/Credits	\$0.00
Balance Due	\$3,702.11

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4344**
 Foreman David Gardner
 Camp Eureka

API# 15-015-24119

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
3-8-19	1242	Seglem #4	16	27 S.	6 E.	Butler	KS
Customer			Safety Meeting	Unit #	Driver	Unit #	Driver
D+J Investments			DG	105	Jason H.		
Mailing Address			JH	113	Caleb G.		
P.O. Box 107			CG				
City	State	Zip Code					
El Dorado	KS	67042					

Job Type Surface Hole Depth 222' KB. Slurry Vol. 30 Bbl Tubing _____
 Casing Depth 201' G.L. Hole Size 12 1/4" Slurry Wt. 15 # Drill Pipe _____
 Casing Size & Wt. 8 5/8" 23 # Cement Left in Casing 15' +/- Water Gal/SK 6.5 Other _____
 Displacement 12.8 Bbl Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 8 5/8 casing. Break circulation w/ 10 Pbl fresh water. Mixed 125 sks Class "A" cement w/ 3% Cacl2, 2% Gel @ 15 #/gal. = 30 Bbl Slurry. Displace w/ 12.8 Bbl fresh water. Shut casing in. Good cement returns to surface = 7 Pbl Slurry to pit. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C101	1	Pump Charge	890.00	890.00
C107	15	Mileage	4.20	63.00
C200	125 sks	Class 'A' Cement	15.75	1968.75
C205	350 #	Cacl2 @ 3%	.63	220.50
C206	235 #	Gel @ 2%	.21	49.35
C108A	5.88 Tons	Ton Mileage	m/c	365.00
			Sub Total	3556.60
			Sales Tax 6.5%	145.51

Thank You

Authorization Witnessed by Charlie Title Lighthouse Dctg. Total 3702.11