

Elite Cementing & Acidizing of KS, LLC
 810 E 7th, PO Box 92
 Eureka, KS 67045



Date	Invoice #
4/25/2019	4465

Bill To	
D&J Investments PO Box 107 El Dorado, KS 67042	
Customer ID#	1242

Job Date	4/23/2019
Lease Information	
Patterson #1	
County	Butler
Foreman	KM

Item	Description	Qty	Terms	Net 15
			Rate	Amount
C101	Cement Pump-Surface	1	890.00	890.00
C107	Pump Truck Mileage (one way)	15	4.20	63.00
C200	Class A Cement-94# sack	125	15.75	1,968.75T
C205	Calcium Chloride	350	0.63	220.50T
C206	Gel Bentonite	235	0.21	49.35T
C108A	Ton Mileage (min. charge)	1	365.00	365.00

We appreciate your business!

Phone #	Fax #	E-mail
620-583-5561	620-583-5524	rene@elitecementing.com

Send payment to:
 Elite Cementing & Acidizing of KS, LLC
 PO Box 92
 Eureka, KS 67045

Subtotal	\$3,556.60
Sales Tax (6.5%)	\$145.51
Total	\$3,702.11
Payments/Credits	\$0.00
Balance Due	\$3,702.11

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report

Ticket No. **4465**
 Foreman Kevin McCoy
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
4-23-19	1242	PATTERSON #1	9	27S	6E	BUTLER	KS
Customer			Unit #	Driver		Unit #	Driver
D & J INVESTMENTS			104	ALAN M.			
Mailing Address			112	CALEB A.			
P.O. Box 107							
City	State	Zip Code					
Eldorado	KS	67042					

Job Type SURFACE Hole Depth 223' KB Slurry Vol. 30 BBL Tubing _____
 Casing Depth 202' G.L. Hole Size 12 1/4 Slurry Wt. 15# Drill Pipe _____
 Casing Size & Wt. 8 5/8 20# Cement Left in Casing 15' Water Gal/SK 6.5 Other _____
 Displacement 13 BBL Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 8 5/8 casing. BREAK CIRCULATION w/ 10 BBL FRESH WATER. MIXED 125 SKS CLASS "A" CEMENT w/ 3% CaCl2, 2% GEL, @ 15#/GAL = 30 BBL SLURRY. DISPLACE w/ 13.0 BBL FRESH WATER. SHUT CASING IN. GOOD CEMENT RETURNS TO SURFACE = 9 BBL TO PIT. JOB COMPLETE. RIG DOWN.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 101	1	Pump Charge	890.00	890.00
C 107	15	Mileage	4.20	63.00
C 200	125 SKS	CLASS "A" CEMENT	15.75	1968.75
C 205	350 #	CaCl2 3%	.63 #	220.50
C 206	235 #	GEL 2%	.21 #	49.35
C 108A	5.88 Tons	Ton Mileage	M/C	365.00
<u>THANK YOU</u> <u>A</u>			Sub Total	3556.60
			Sales Tax	145.51
Authorization <u>Witnessed By CHARLIE COLTIER</u> Title _____			Total	3702.11

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.