



PAGE 1 of 1	CUST NO 1000606	YARD # 1718	INVOICE DATE 02/07/2019
INVOICE NUMBER 92905928			

Pratt (620) 672-1201
 B CARL E. GUNGOLL EXPLORATION INC
 I PO Box: 18466
 L OKLAHOMA CITY
 L OK US 73154
 T
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME Cutter East 416 **16373.64**
 O LOCATION
 B COUNTY Haskell
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41159695			Net - 30 days	03/09/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
For Service Dates: 02/06/2019 to 02/06/2019				
0041159695				
171817270L Cement-New Well Casing/Pi 02/06/2019 Cement Surface Casing				
A-Con' Blend	400.00	EA	12.09	4,836.00 T
150 Sks. - Premium Plus Cement	1.00	EA	1,590.00	1,590.00 T
138 Lbs. - Celloflake	1.00	EA	332.58	332.58 T
1410 Lbs. - Calcium Chloride	1.00	EA	958.80	958.80 T
C-51	76.00	LB	16.25	1,235.00 T
Top Rubber Cement Plug, 8 5/8"	1.00	EA	225.00	225.00
Guide Shoe - Regular, 8 5/8" (Blue)	1.00	EA	380.00	380.00
Flapper Type Insert Float Valves. 8 5/8"	1.00	EA	280.00	280.00
Centralizer, 8 5/8" (Blue)	12.00	EA	90.00	1,080.00
Industrial Rubber Thread Lock Kit	1.00	EA	34.00	34.00
135 Miles/Heavy Equipment Mileage	1.00	MI	658.80	658.80
Blending & Mixing Service Charge	550.00	BAG	0.91	500.50
1163 Tn/Mi-Proppant & Bulk Del. Chg.	1.00	EA	1,895.69	1,895.69
Depth Charge; 1001'-2000'	1.00	EA	975.00	975.00
Plug Container Utilization Charge	1.00	EA	162.50	162.50
45 Miles/Unit Mileage Chg	1.00	MI	131.85	131.85
"Service Supervisor, first 8 hrs on loc.	1.00	EA	113.75	113.75
Cement Data Acquisition Monitor	1.00	EA	357.50	357.50

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	15,746.97
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	626.67
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	16,373.64
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING Job Log

Customer:	Carl E. Gungoll	Cement Pump No.:	38119-19570 8 HRS	Operator TRK No.:	96815
Address:		Ticket #:	1718-17270 L	Bulk TRK No.:	14354-19578 19827-19808
City, State, Zip:		Job Type:	Z42 - Cement Surface Casing		
Service District:	1718 - Liberal Ks	Well Type:	OIL		
Well Name and No.:	Cutter East 416	Well Location:	4,31,34	County:	Haskell
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
A-CON BLEND	400	3%CaCl, 1/4#POLYFLAKE, .2%WCA-1	14354-19578	Front	Back
PREMIUM PLUS	150	2%CaCl, 1/4#POLYFLAKE	19827-19808	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	11.4	2.95	18.1	1180	Man Hours:	38
Tail:	14.8	1.34	6.33	201	# of Men on Job:	3

Time (am/pm)	BPM	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
17:30							ON LOC, SAFTEY MTG, R.U.
1:30						2000	TEST LINES
1:34 AM	5.4					110	START LEAD @ 11.4#
2:04 AM	5.1	210				90	START TAIL @ 14.8#
2:17 AM		36					SHUT DOWN, DROP PLUG
2:19	5					30	START DISPLACEMENT, WASHUP
2:38	3	71				250	SLOW RATE
2:49 AM		104				500-1000	PLUG DOWN
2:52							RELEASE PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	12 1/4	Depth			TYPE	
Size & Wt. Csg.	8 5/8 24	Depth	1675.18	New / Used	Packer	Depth
tbg.		Depth			Retainer	Depth
Top Plugs		Type			Perfs	CIBP

Customer Signature:

Basic Representative: CHAD HINZ

Basic Signature:

Date of Service: 2/6/2019