



PAGE 1 of 1	CUST NO 1000606	YARD # 1718	INVOICE DATE 02/11/2019
INVOICE NUMBER 92907365			

580209-01 8

Pratt (620) 672-1201
 B CARL E. GUNGOLL EXPLORATION INC
 I PO Box: 18466
 L OKLAHOMA CITY
 L OK US 73154
 T
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME Cutter East 416
 O LOCATION
 B COUNTY Haskell
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T
 E JOB CONTACT

14132.50

JOB # 41160254	EQUIPMENT #	PURCHASE ORDER NO.	TERMS Net - 30 days	DUE DATE 03/13/2019
-------------------	-------------	--------------------	------------------------	------------------------

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 02/10/2019 to 02/10/2019</i>				
0041160254				
171817275L Cement-New Well Casing/Pi 02/10/2019 Cement Production Casing				
A-Con' Blend	150.00	EA	12.09	1,813.50 T
AA2 Cement	200.00	EA	11.83	2,366.00 T
38 Lbs. - Celloflake	1.00	EA	91.58	91.58 T
423 Lbs. - Calcium Chloride	1.00	EA	287.64	287.64 T
940 Lbs. - Gypsum	1.00	EA	460.60	460.60 T
C-17	94.00	LB	13.00	1,222.00 T
C-41P	47.00	LB	2.60	122.20 T
1108 Lbs. - Salt	1.00	EA	365.64	365.64 T
1000 Lbs. - Gilsonite	1.00	EA	440.00	440.00 T
Auto Fill Float Shoe 5 1/2" (Blue)	1.00	EA	360.00	360.00 T
Latch Down Plug & Baffle, 5 1/2" (Blue)	1.00	EA	400.00	400.00 T
Turbolizer, 5 1/2" (Blue)	10.00	EA	110.00	1,100.00 T
90 Miles - Heavy Equipment Mileage	1.00	MI	439.20	439.20 T
Blending & Mixing Service Charge	350.00	BAG	0.91	318.50 T
740 Tn/Mi-Proppant & Bulk Del. Chg.	1.00	EA	1,206.20	1,206.20 T
Depth Charge; 5001-6000'	1.00	EA	1,872.00	1,872.00 T
Plug Container Util. Chg.	1.00	EA	162.50	162.50 T
45 Miles - Unit Mileage Chg	1.00	MI	131.85	131.85 T
"Service Supervisor, first 8 hrs on loc.	1.00	EA	113.75	113.75 T
Cement Data Acquisition Monitor	1.00	EA	357.50	357.50 T

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	13,630.66
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	501.84
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	14,132.50
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log


Customer:	Carl E. Gungoll	Cement Pump No.:	38119-19570 6 HRS	Operator TRK No.:	96815
Address:		Ticket #:	1718-17275 L	Bulk TRK No.:	19827-19808
City, State, Zip:		Job Type:	Z42 - Cement Production Casing		
Service District:	1718 - Liberal Ks	Well Type:	OIL		
Well Name and No.:	Cutter East 416	Well Location:	4,31,34	County:	Haskell
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
A CON BLEND	150	3%CaCl, 1/4#POLYFLAKE	19827-19808	Front	Back
AA2	200	10%GYPSUM, 10%SALT, 5#GILSONITE, .5%C-17, 1/4#DEFOAMER		Front	Back
				Front	Back


Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	11.4	2.95	18.1	442.5	Man Hours:	28
Tail:	14.8	1.51	6.65	302	# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
5:20							ON LOC, SAFTEY MTG, R.U.
10:40							PLUG RAT & MOUSE
11:02 AM						4000	TEST LINES
11:04 AM	6					150	START LEAD @ 11.4#
11:12 AM	6.5	52.5				150	ON TAIL @ 14.8#
11:22		53.8					SHUT DOWN, DROP PLUG, WASHUP
11:27	7					30	START DISPLACEMENT
11:46 AM	3.5	117				890	SLOW RATE
11:49		127				1200-1800	PLUG DOWN
11:52							RELEASE PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	7 7/8	Depth				TYPE	
Size & Wt. Csg.	5 1/2 15.5	Depth	5385.96	New / Used	NEW	Packer	Depth
tbg.		Depth				Retainer	Depth
Top Plugs		Type				Perfs	CIBP

Customer Signature: 


Basic Representative: CHAD HINZ

Basic Signature: 

Date of Service: 2/10/2019

GUNGOLL

CEU4-16



Job Started On: 02/10/2019 @ 10:40:35 AM