

QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1261

Date	4-10-19	Sec.	20	Twp.	8	Range	18	County	Rooks	State	Ks	On Location		Finish	11:00 AM				
Lease	Pittman-Carster			Well No.	1			Location Plainville - N to N Rd, 1W, 1/2S, 1/2W											
Contractor	Southwind			#1				Owner to 15 Rd, 1S to P Rd, 1/2 W, 5/4 into											
Type Job	Bottom Stage						To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.												
Hole Size	7 7/8"			T.D.	3520'			Charge To Jason oil											
Csg.	3 1/2" 14#			Depth	3517.83'			Street											
Tbg. Size				Depth				City State											
Tool	DU Tool			Depth	1863'			The above was done to satisfaction and supervision of owner agent or contractor.											
Cement Left in Csg.	24.90'			Shoe Joint	24.90'			Cement Amount Ordered 185 Q Pro-C 10% Salt 5% Gilsen											
Meas Line	40 mind 45 1/4 water			Displace	85 1/4 BUS			500 gal Mud Clear											
EQUIPMENT												Common							
Pumptrk	17	No.	Cementer	David	Rick			Poz. Mix											
			Helper																
Bulktrk	9	No.	Driver	Doug	Michael			Gel.											
			Driver																
Bulktrk	17	No.	Driver	Jack				Calcium											
			Driver																
JOB SERVICES & REMARKS												Hulls							
Remarks:													Salt						
Rat Hole													Flowseal						
Mouse Hole													Kol-Seal						
Centralizers	J#s - 8, 5, 7, 9, 11, 13, 42												Mud CLR 48						
Baskets	4, 12, 43, 54, 68												CFL-117 or CD110 CAF 38						
DN or Port Collar	#43 1863'												Sand						
pipe on bottom, break Circulation												Handling							
pump 500 gal mud clear, 2 BUS												Mileage							
spacer, mix 185 sx Cement.												FLOAT EQUIPMENT							
shut down, wash pump + lines												Guide Shoe DU Tool w/plug							
Displaced plug w/ 85 1/4 BUS #20.												Centralizer 7							
Released + held. r mud												Baskets 5							
Drop Dart + open tool 800 #												AFU Inserts							
												Float Shoe 1							
Lift pressure 800 #												Latch Down							
Land plug to 1500 #																			
Break Circulation																			
												Pumptrk Charge							
												Mileage							
												Tax							
												Discount							
												Total Charge							

[Signature]
Signature