



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

100707
40909

INV 901054

TICKET NUMBER 55565
LOCATION Ottawa, Ks.
FOREMAN Jim Green

FIELD TICKET & TREATMENT REPORT
CEMENT

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY |
|--|------------|-------------------------------|--------------------------|-----------------------|-------|--------|
| 07-02-19 | 6370 | Knabe A #6 | SE 30 | 14 | 22 | JO |
| CUSTOMER <u>PTI INC</u> | | | | | | |
| MAILING ADDRESS <u>801 West 47th St Ste 412</u> | | | | | | |
| CITY <u>Kansas City</u> | | STATE <u>Mo.</u> | ZIP CODE <u>64112</u> | | | |
| JOB TYPE <u>Longstring</u> | | HOLE SIZE <u>5 7/8"</u> | HOLE DEPTH <u>967'</u> | CASING SIZE & WEIGHT | | |
| CASING DEPTH <u>937'</u> | | DRILL PIPE <u>Buttle 903'</u> | TUBING | OTHER | | |
| SLURRY WEIGHT | | SLURRY VOL | WATER gal/sk | CEMENT LEFT in CASING | | |
| DISPLACEMENT | | DISPLACEMENT PSI | MIX PSI | RATE | | |

| TRUCK # | DRIVER | TRUCK # | DRIVER |
|---------|---------|---------|--------|
| 669 | Jim Gre | | |
| 485 | Har Bel | | |
| 675 | Gas Ken | | |
| 775 | Ala Mad | | |

REMARKS: Held safety meeting. Establish circulation. Mix and pump 100' gel to flush. Pump 5 BBLs clean water. Mix and pump 1175K Poz-Blend IA with 2% Gel + 1/4" F10 Seal. Circulate cement to surface. Flush pump clear of cement. Pump 2 1/2" rubber plug to total depth of casing. Pressure up to 800" PSI. well held good. See flow.

| ACCOUNT CODE | QUANTITY or UNITS | DESCRIPTION of SERVICES or PRODUCT | UNIT PRICE | TOTAL |
|--------------|-------------------|------------------------------------|--------------------|-----------|
| ✓ CE0450 | 1 | PUMP CHARGE | 1500 ⁰⁰ | |
| ✓ CE0802 | 30 | MILEAGE Pump TK | 214.58 | |
| ✓ CE0711 | min | Ten Mileage | 600 ⁰⁰ | |
| ✓ WE0853 | 2.5 HRS | VAL TK | 250 ⁰⁰ | |
| | | Sub Total | 2624.58 | |
| | | Less -40% | 1049.83 | 1574.75 |
| ✓ SUM | | | | |
| ✓ CL5840 | 117 SK | Poz-Blend IA | 1079.50 | |
| ✓ CL5965 | 297 # | Gel | 89.10 | |
| ✓ CL6075 | 29 # | F10-Seal | 58 ⁰⁰ | |
| ✓ CP8176 | one | 2 1/2" Rubber Plug | 45 ⁰⁰ | |
| | | Sub Total | 1771.60 | |
| | | Less -40% | 708.64 | 1062.96 |
| | | | | \$2037.04 |
| | | 7.975% SALES TAX | 184.77 | |
| | | ESTIMATED TOTAL | | 2221.81 |

Ravn 3737

AUTHORIZATION

TITLE 07-02-19

DATE (453739)

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.