



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

100724
 40923

INV 901070

TICKET NUMBER 55598
 LOCATION Ottawa, KS
 FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/8/19	6370	Kwabe A # 6-I	SE 30	14	22	JO
CUSTOMER Petroleum Technologies			TRUCK #			
MAILING ADDRESS 801 W. 47th St. Ste 412			DRIVER			
CITY Kansas City			TRUCK #			
STATE MO			DRIVER			
ZIP CODE 64112			TRUCK #			
			DRIVER			

JOB TYPE logstring HOLE SIZE 5 5/8" HOLE DEPTH 960' CASING SIZE & WEIGHT 2 7/8" EUE
 CASING DEPTH 939' DRILL PIPE _____ TUBING baffle - 904' OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 35'
 DISPLACEMENT 5.23 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 200#
Bentonite followed by 5 bbls fresh water, mixed & pumped 135 sks
Pozblend 1A cement w/ 2% Bentonite + 1/4 # Floseal per sk, cement
to surface, flushed pump clean, pumped 2 1/2" rubber plug to baffle
w/ 5.23 bbls fresh water, pressured to 800 PSI, well held pressure for
30 min MIT, released pressure to set float valve.

Handwritten signature/initials

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ CE0450	1	PUMP CHARGE	1500.00	
✓ EC0002	30 mi	MILEAGE	214.50	
✓ EO711	min	ten mileage	160.00	
✓ WE0853	2 hrs	80 Vac	200.00	
		trucks	2574.50	
		-40%	1029.80	
		subtotal		1544.70
✓ CC5840	135 sks	Pozblend 1A cement	1822.50	
✓ CC5965	427 #	Bentonite	128.10	
✓ CC6075	34 #	Floseal	68.00	
✓ CP8176	1	2 1/2" rubber plug	45.00	
		materials	2063.60	
		-40%	825.44	
		Subtotal		1238.16
				<u>2782.86</u>
		7.975%	SALES TAX	98.74
			ESTIMATED TOTAL	2881.60
				(4802.67)

Revin 3737

AUTHORIZATION _____ TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.