



PRESSURE PUMPING LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

100725
40924

INV 901071

TICKET NUMBER 55599

LOCATION Ottawa, KS

FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/9/19	6370	Knabe A # 10-I	SE 30	14	22	JO
CUSTOMER <u>Petroleum Technologies Inc</u>						
MAILING ADDRESS <u>801 W. 47th St. Ste 412</u>						
CITY <u>Kansas City</u>		STATE <u>MO</u>	ZIP CODE <u>66112</u>			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			<u>729</u>	<u>Case Kan</u>	<u>✓ Safety Meeting</u>	
			<u>495</u>	<u>Har Bec</u>	<u>✓</u>	
			<u>775</u>	<u>Ala Mad</u>	<u>✓</u>	
			<u>675</u>	<u>Kei Det</u>	<u>✓</u>	

JOB TYPE long string HOLE SIZE 5 5/8" HOLE DEPTH 946' CASING SIZE & WEIGHT 2 7/8" CUE
 CASING DEPTH 926' DRILL PIPE _____ TUBING baffle - 896' OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 30'
 DISPLACEMENT 5.19 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 200 # Bentonite followed by 5 bbls fresh water, mixed & pumped 133 SKS Pozblend 1A cement w/ 2% Bentonite & 1/4 # Floeal per SK, cement to surface flushed pump clean, pumped 2 1/2" rubber plug to baffle w/ 5.19 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MIT, released pressure to set float valve.

Handwritten signature/initials

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ CE0450	1	PUMP CHARGE	1500.00	
✓ CE0002	30 mi	MILEAGE	214.50	
✓ CE0711	min	for mileage	660.00	
✓ WE0853	2 hrs	80 Vac	200.00	
		trucks	2574.50	
		-40%	1029.80	
		Subtotal		1544.70
✓ CC5840	133 SKS	Pozblend 1A cement	1795.50	
✓ CC5965	423 #	Bentonite	126.90	
✓ CC6075	33 #	Floeal	66.00	
✓ CP8176	1	2 1/2" rubber plug	45.00	
		materials	2033.40	
		-40%	813.36	
		Subtotal		1220.04
		7.975%	SALES TAX	97.30
			ESTIMATED TOTAL	2862.04
				(4770.06)

Ravin 3737

AUTHORIZATION No Co Rep on location TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.