



PRESSURE PUMPING LLC  
PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

100754  
40952

TICKET NUMBER 55600  
LOCATION Ottawa, KS  
FOREMAN Cassey Kennedy

FIELD TICKET & TREATMENT REPORT  
CEMENT

INV# 901092

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/11/19	6370	Knabe A # 14-I	SE 30	14	22	JO
CUSTOMER Petroleum Technologies Inc.			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 801 W. 47th St. Ste 412			729 Casken ✓ Safety Meeting			
CITY STATE ZIP CODE Kansas City MO 64112			495 HarBec ✓			
			611 AlMad ✓			
			675 KeiDet ✓			

JOB TYPE longstring HOLE SIZE 5 5/8" HOLE DEPTH 980' CASING SIZE & WEIGHT 2 7/8" EUE  
 CASING DEPTH 957' DRILL PIPE \_\_\_\_\_ TUBING baffle - 922' OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 35'  
 DISPLACEMENT 5.34 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 5.5 bpm

REMARKS: held safety meeting, established circulation, washed down 6 joints of casing, mixed & pumped 200# Bentonite followed by 5 bbls fresh water, mixed & pumped 136 sks Pozblend 1A cement w/ 2% + 1/4 # Floreal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to baffle w/ 5.34 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MIT, released pressure to set float valve.

*AK*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450 ✓	1	PUMP CHARGE	1500.00	
CE0002 ✓	30 mi	MILEAGE	214.50	
CE0711 ✓	min	ton mileage	660.00	
WE0853 ✓	3 hrs	80 Vac	300.00	
		trucks	2674.50	
		- 40%	1069.80	
		Subtotal		1604.70
CC5840 ✓	136 sks	Pozblend 1A cement	1836.00	
CC5965 ✓	428 #	Bentonite	128.40	
CC6075 ✓	34 #	Floreal	68.00	
CP8176 ✓	1	2 1/2" rubber plug	45.00	
		materials	2077.40	
		- 40%	830.96	
		Subtotal		1246.44
		7.975%	SALES TAX	99.40
			ESTIMATED TOTAL	2950.54

AUTHORIZATION No Co Rep TITLE \_\_\_\_\_ DATE (4917.57)

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

