



PRESSURE PUMPING LLC  
PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

100757

40955

TICKET NUMBER 55602  
LOCATION Ottawa, KS  
FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT  
CEMENT

INV # 901095

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY			
7/12/19	6370	Knabe A #5-A	SE 30	14	22	JO			
CUSTOMER Petroleum Technologies Inc									
MAILING ADDRESS 801 W. 47th St. Ste 412									
CITY Kansas City		STATE MO	ZIP CODE 64112						
		TRUCK #		DRIVER		TRUCK #		DRIVER	
		729		Coker		✓		Safety Meeting	
		495		HarBec		✓			
		775		AlaMad		✓			
		675		KeiDet		✓			

JOB TYPE longstring HOLE SIZE 5 5/8" HOLE DEPTH 970' CASING SIZE & WEIGHT 2 7/8" CUE  
CASING DEPTH 934' DRILL PIPE TUBING baffle - 899' OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 35'  
DISPLACEMENT 5.20 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 230# Bentonite followed by 8 bbls fresh water, mixed & pumped 128 sks Portland IA cement w/ 2% Bentonite & 1/4 # Floreal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to baffle w/ 5.20 bbls fresh water, pressured to 800 PSI, released pressure to set float valve.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450 ✓	1	✓ PUMP CHARGE	1500.00	
CE0002 ✓	30 mi	✓ MILEAGE	214.50	
CE0711 ✓	min	✓ taxi mileage	660.00	
WE0853 ✓	2 hrs	✓ 80 Vac	200.00	
		trucks	2574.50	
		-40%	1029.80	
		subtotal		1544.70
51558 CC5840 ✓	128 sks	✓ Portland IA cement	1728.00	
CC5965 ✓	415 #	✓ Bentonite	124.50	
CC6075 ✓	32 #	✓ Floreal	64.00	
CP8176 ✓	1	✓ 2 1/2" rubber plug	45.00	
		materials	1961.50	
		-40%	784.60	
		Subtotal		1176.90
		7.975%	SALES TAX	93.86
			ESTIMATED TOTAL	2815.46

AUTHORIZATION \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_

SCANNED

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

