

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: _____
 Name: _____
 Address 1: _____
 Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Contact Person: _____
 Phone: (_____) _____
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - _____
 Spot Description: _____
 _____ - _____ - _____ - _____ Sec. _____ Twp. _____ S. R. _____ East West
 _____ Feet from North / South Line of Section
 _____ Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: _____
 Lease Name: _____ Well #: _____
 Date Well Completed: _____
 The plugging proposal was approved on: _____ (Date)
 by: _____ (KCC District Agent's Name)
 Plugging Commenced: _____
 Plugging Completed: _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging Contractor License #: _____ Name: _____
 Address 1: _____ Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Phone: (_____) _____
 Name of Party Responsible for Plugging Fees: _____
 State of _____ County, _____, ss.
 _____ Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4617**
 Foreman David Gardner
 Camp Eureka

API # 15-031-19110

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
8-2-19	1000	Kelly # 5 OLD	14	23 S.	13 E.	Coffey	KS
Customer			Unit #	Driver	Unit #	Driver	
Trimble & Maclasley Oil LLC			105	Jason			
Mailing Address			Safety Meeting				
P.O. Box 171			DG	112	Jason		
			JH	113	Steve		
			SM	145	Steve		
City	State	Zip Code					
Gridley	KS	66852					

Job Type P.T.A. Old Well Hole Depth 1833' Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth 1750' Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 2 3/8" Tubing. Plug well as follows:


35 SKS Class 'A' Cement w/ 3% Caclz + 2" Phenoseal/sk @ 11672'
Wait 1 HR Tag cement w/ Wireline @ 1366'
Gel Spacer
30 SKS Class 'A' Cement w/ 3% Caclz + 2" Phenoseal/sk @ 850'
Wait 1 HR Tag cement w/ Wireline @ 525'
Gel Spacer
100 SKS 60/40 Pozmix Cement w/ 4% Gel @ 250' to Surface
165 SKS Total

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	785.00	785.00
C107	35	Mileage	4.20	147.00
C200	65 SKS	Class 'A' Cement	15.75	1023.75
C205	185 #	Caclz @ 3%	.63	116.55
C208	130 #	Phenoseal @ 2"/sk	1.30	169.00
C203	100 SKS	60/40 Pozmix Cement	13.40	1340.00
C206	350 #	Gel @ 4%	.21	73.50
C108A	7.355 Tons	Ton Mileage - Bulk Trucks	m/c	365.00
C206	300 #	Gel Spacer	.21	63.00
C113	4 HRS	80 Bbl Vac Truck	90.00 / HR	360.00
C224	3300 gals	City Water	10.00 / 1000 gals	33.00
			Sub Total	4,475.80
			Less 5%	238.34
			Sales Tax	290.93
			6.5%	

Thank You

Authorization _____ Title _____ Total **4,528.39**

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.



MIDWEST SURVEYS

LOGGING • PERFORATING • CONSULTING • M.I.T. SERVICES

P.O. Box 68 • Osawatomie, KS 66064
Phone 913-755-2128 • Fax 913-755-6533

Perforation Record

Company: TRIMBLE & MACLASKEY OIL, LLC

Lease/Field: KELLY LEASE

Well: # 5-OLD

County, State: COFFEY COUNTY, KANSAS

Service Order #: 37445

Purchase Order #: N/A

Date: 7/26/2019

Perforated @: 249.0 TO 250.0 2 PERFS
849.0 TO 850.0 2 PERFS
CEMENT SQUEEZE

Type of Jet, Gun or Charge: 3 1/2" STICK JETS

Number of Jets, Guns or Charges: FOUR (4) PERFORATIONS

Casing Size: 4/12"