



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

100375
 40580

TICKET NUMBER 55551
 LOCATION BHawa, KS
 FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
 CEMENT

Invoice # 900105

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4/11/19	6907	Lewis # R2-19	SE 22	33	12	CO
CUSTOMER Reata Petroleum LLC			TRUCK #			
MAILING ADDRESS PO Box 111			DRIVER		TRUCK #	
CITY Independence			DRIVER		TRUCK #	
STATE KS			DRIVER		TRUCK #	
ZIP CODE 67301			DRIVER		TRUCK #	
			DRIVER		TRUCK #	

JOB TYPE long string HOLE SIZE 5 7/8" HOLE DEPTH 1153' CASING SIZE & WEIGHT 2 7/8" EUE
 CASING DEPTH 1128' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 6.53 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 100# Bentonite followed by 5 bbls fresh water, mixed + pumped 141 sks Pozblend IIIA cement w/ 4% Bentonite, 2% Calcium Chloride, 5 # Kalseal + 1# Phenoseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 6.53 bbls fresh water, pressured to 800 PSI, release pressure to set float valve.

Handwritten signature

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	65 mi	MILEAGE	464.75	
CE0711	min	ton mileage	660.00	
WS 2402	2 hrs	Transport	240.00	
		trucks	2804.75	
		-39%	1117.25	
		subtotal		1747.50
CC5846	141 sks	Pozblend IIIA cement	2326.50	
CC5965	596 #	Bentonite	178.80	
CC6077	705 #	Kalseal	352.50	
CC6079	141 #	Phenoseal	190.35	
CP8176	1	2 1/2" rubber plug	45.00	
		materials	3093.15	
		-39%	1206.33	
		subtotal		1886.82
		8.5%	SALES TAX	160.38
		ESTIMATED TOTAL		3794.70
		DATE		(16220.82)

SCANNED

Ravin 3737

AUTHORIZATION

Handwritten signature

TITLE

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form