

10 E 7TH
 O Box 92
 EKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4346**
 Foreman David Cochran
 Camp Encke

11-15-115-21505

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
3-10-19	1284	Burton #9	15	23 S	4 E	Marion	KS	
Customer Driller's + Producer's Ten			Safety Meeting D6 11M 2H 5M AM		Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 385					104	Blair M.		
City Marion					116	Zeke H.		
State KS					113	Steve B.		
Zip Code 67104					141	Kevin M.		

Job Type Logging Hole Depth 2181' KB Slurry Vol. 146 Bbl Tubing _____
 Casing Depth 2723-20' 64 Hole Size 7 7/8 Slurry Wt. 12.2% Drill Pipe _____
 Casing Size & Wt. 5 1/2" 17" Cement Left in Casing _____ Water Gal/SK 83 Other _____
 Displacement 65 Bbl Displacement PSI 1500 Bump Plug to 1500 PSI BPM 5

Remarks: Safety Meeting. Drop Pencil ball. Rig up to 5 1/2" casing. Break circulation w/ 15 Bbl fresh water. Set Basket Size @ 11 Bbl @ 900 PSI. Mixed 450 sks 60/40 Pozmax Cement w/ 16% Gel, 2" Phosocal / sk @ 12.2% / gal, yield 1.75 = 146 Bbl Slurry. Wash out Pump + Lines. Shut down. Released 5 1/2" Top Rubber Plug. Dumped plug + seat w/ 65 Bbl fresh water. Final pumping pressure of 1000 PSI. Pump plug to 1500 PSI. Good cement returns to surface = 7 Bbl slurry to pit. Released pressure. Floct + Plug held. Good circulation @ all times while cementing. Job complete. Rig down.

Plus Reticle w/ 20 sks + Phosocal w/ 15 sks.
Centralizers - 13,57. Encke 15 - 174.25

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	1100.00	1100.00
C107	25	Mileage	4.20	105.00
C203	450 sks	60/40 Pozmax Cement	13.40	6030.00
C206	2320"	Gel @ 16%	.21	487.20
C208	900"	Phosocal @ 2"/sk	1.30	1170.00
C108A	12.35 Ten	Ten Mileage - Pail Trucks	1.40	677.25
C113	5 HRS	30 Bbl Vac Truck	90.00 / HRS	450.00
C774	3300 Gals	City Water	1000/1000 Gals	33.00
C761	1	5 1/2" Type B Basket Size	1355.00	1355.00
C504	4	5 1/2" Centralizers	50.00	200.00
C604	2	5 1/2" Cement Baskets	236.00	472.00
C404	1	5 1/2" Top Rubber Plug	74.00	74.00
			Sub Total	12153.45
			Less 5%	644.90
			7.5%	Sales Tax
				736.59
Authorization _____ Title _____			Total	12,245.14

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

810 E 7TH
 PO Box 92
 UREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
4389
 Ticket No. _____
 Foreman MUSSEN MCGEE
 Camp ELITE A

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
5-6-17	1871	Rustow # 7	18	22	4	Marion	KS	
Customer <u>Denon + Products Inc.</u>			Safety Meeting <u>10M AD 2000</u>		Unit #	Driver	Unit #	Driver
Mailing Address <u>P.O. Box 388</u>					<u>105</u>	<u>AD</u>		
City <u>Newton</u>			State <u>Ks</u>		Zip Code <u>67114</u>			

Job Type SIP Hole Depth 224 EB Slurry Vol. _____ Tubing _____
 Casing Depth 34 6L Hole Size 11.75 Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 8.50 Cement Left in Casing 20 Water Gal/SK _____ Other _____
 Displacement 11.94 Displacement PSI _____ Bump Plug to _____ BPM 5

Remarks: Safety + job procedure meeting. 5:10 to 8:30 casing break circulation
of 10 gal water mix + pump 10 gal 20" dia w/ 3% cacl2 27 gal = 37 gal
Slurry @ 14.8" diameter of 224 gal water 4 gal gas cement returned to
surface. Close casing. Job complete. TDR 2000.
Thank you
Mussen McGee

Code	Qty or Units	Description of Product or Services	Unit Price	Total
A 201	1	Pump Charge	840.00	840.00
A 107	35	Mileage	30.00	1050.00
C 200	115	SKI class A cement	15.75	1811.25
C 203	325	cacl2 = 3%	6.2	2017.5
C 206	200	gal = 2%	2.1	420.00
E 108 A	5.4	Tax Tax Mileage	64.00	345.60
			<u>Sub Total</u>	<u>3368.00</u>
			<u>- 5%</u>	<u>168.40</u>
			Sales Tax	<u>9.27</u>

Authorization authorized by John Gabel Title Tool Pusher Total 3546.23

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.