


10857

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. **4445**  
 Foreman David Gardner  
 Camp Eureka

API # 15-191-22912

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
4-17-19		Van Zant #1	23	34S	1W	Sumner	KS	
Customer <u>Energy Partners, LLC</u>			Unit #		Driver		Unit #	Driver
Mailing Address <u>8918 West 21<sup>st</sup> Street North #200-304</u>			105		Jason			
City <u>Wichita</u>			112		Zion			
State <u>KS</u>								
Zip Code <u>67205</u>								

Job Type Longstring Hole Depth 4451' KB. Slurry Vol. 59 Bbl Tubing \_\_\_\_\_  
 Casing Depth 4415.11' G.L. Hole Size 7 7/8" Slurry Wt. 13.6" Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2" Cement Left in Casing 4 Water Gal/SK 9.0 Other \_\_\_\_\_  
 Displacement 110.5 Bbl Displacement PSI 1750 Bump Plug to 1750 BPM 5

Remarks: Safety Meeting. Rig up to 5 1/2" casing. Break circulation w/ 20 Bbl fresh water. Mixed 185 sacks Thick Set Cement w/ 5" KelSeal /SK, 1" Phone Seal /SK @ 13.6"/gal, yield 1.80 = 59 Bbl Slurry. Wash out pump & lines. Shut down. Released 5 1/2" Latch Down Plug. Displaces plug to seat w/ 110.5 Bbl fresh water. (KCL is 1<sup>st</sup> 40 Bbl displacement water). Final pumping pressure of 1250 PSI. Pump plug to 1750 PSI. Release pressure. Float & Plug hold grid. Good circulation @ all times while cementing. Job complete. Rig dump.

Note: New & Used Casing. Plug Blocks w/ 15 sacks & Roth hole w/ 20 sacks  
 Basket on #120 Centralizers on #120, 122, 124, 126, 128, 132, 134, 136.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	1100.00	1100.00
C107	100	Mileage	4.20	420.00
C201	185 sacks	Thick Set Cement	20.50	3792.50
C207	925"	KelSeal @ 5"/SK	.47	434.75
C208	185"	Phone Seal @ 1"/SK	1.30	240.50
C661	1	5 1/2" NFU Float Shoe	309.00	309.00
C609	1	5 1/2" Cement Basket	236.00	236.00
C504	8	5 1/2" Centralizers	50.00	400.00
C481	1	5 1/2" Latch Down Plug	242.00	242.00
C222	10 gals	KCL - In 1 <sup>st</sup> 40 Bbl Displacement water.	30.00	300.00
C108B	10.175 Tons	Ton Mileage - Bulk Truck	140	1424.50
<u>Thank You</u>			Sub Total	8899.25
			Less 5%	467.29
			<b>Sales Tax</b>	446.61

Authorization [Signature] Title \_\_\_\_\_ Total 8878.57

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.