

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4617**
 Foreman David Gardner
 Camp Eureka

API # 15-031-19110

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
8-2-19	1000	Kelly # 5 OLD	14	23 S.	13 E.	Coffey	KS
Customer			Unit #	Driver	Unit #	Driver	
Trimble & Maclasley Oil LLC			105	Jason			
Mailing Address			112	Jason			
P.O. Box 171			113	Steve			
City	State	Zip Code	145	Steve			
Gridley	KS	66852					

Job Type P.T.A. Old Well Hole Depth 1833' Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth 1750' Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 2 3/8" Tubing. Plug well as follows:

35 SKS Class 'A' Cement w/ 3% Caclz + 2" Phenoseal/sk @ 11672'
Wait 1 HR Tag cement w/ Wireline @ 1366'
Gel Spacer
30 SKS Class 'A' Cement w/ 3% Caclz + 2" Phenoseal/sk @ 850'
Wait 1 HR Tag cement w/ Wireline @ 525'
Gel Spacer
100 SKS 60/40 Pozmix Cement w/ 4% Gel @ 250' to Surface
165 SKS Total

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	785.00	785.00
C107	35	Mileage	4.20	147.00
C200	65 SKS	Class 'A' Cement	15.75	1023.75
C205	185 #	Caclz @ 3%	.63	116.55
C208	130 #	Phenoseal @ 2"/sk	1.30	169.00
C203	100 SKS	60/40 Pozmix Cement	13.40	1340.00
C206	350 #	Gel @ 4%	.21	73.50
C108A	7.355 Tons	Ton Mileage - Bulk Trucks	m/c	365.00
C206	300 #	Gel Spacer	.21	63.00
C113	4 HRS	80 Bbl Vac Truck	90.00 / HR	360.00
C224	3300 gals	City Water	10.00 / 1000 gals	33.00
			Sub Total	4,475.80
			Less 5%	238.34
			Sales Tax	290.93
				6.5%

Thank You

Authorization _____ Title _____ Total **4,528.39**

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.