

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Received 6 August 2019
Cement or Acid Field Report
Ticket No. 4616
 Foreman David Gardner
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
7-31-19	1008	Barker #4	2	25S	8E	Greenwood	KS
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
Jackson Brothers LLC	116 E. 3 rd	Eureka	KS	67045	DG JH CE AM	105 114 141	Jason Caleb Alan M.

Job Type P.T.A. Oldwell Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth 2336 FT. Hole Size 7-7/8" Slurry Wt. 14# Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK 6.5 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting. Rig up to 2 3/8" Tubing. Plug well as follows:
Bottom Plug set by Long Drilling.
20 sks @ 1065'
Gel Spacer
130 sks @ 250' to Surface - Cement fell back
150 sks Total

8-6-19 - Tag cement @ 135' w/wireline. Fill up w/ 10 sks cement.
Ran 1" down annulus of 4 1/2 casing, wash down & tag firm cement @ 198'.
Circulate cement to surface w/ 35 sks cement. Pull 1" & wash up. Job complete. Rig down

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	785.00	785.00
C107	15	Mileage	4.20	63.00
C203	195 sks	60/40 Pozmix Cement	13.46	2613.00
C206	670 #	Gel @ 4%	.21	140.70
C108A	8.385 Tons	Ton Mileage - Bulk Truck	m/c	365.00
C206	200 #	Gel Spacer	.21	42.00
C113	4 HRS	80 Bbl Vac Truck	90.00 /HR	360.00
C224	3000 gals	City Water	10.00/1000 gals	30.00
<u>Thank You</u>				
			Sub Total	4,398.70
			Less 5%	237.53
			8.0% Sales Tax	351.90

Authorization Roseanne H. Jackson II Title CO-MANAGER Total 4,513.07

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.