

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **4690**
Foreman Kevin McCoy
Camp EUREKA

API # 15-073-19890

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
8-21-19	1000	ShadeL #1 old	15	23S	13E	6W	Ks
Customer <u>Trimble & MacLasky OIL LLC</u>			Safety Meeting Unit # 104 113 145		Driver ALAN M. Josh V. Steve M.		Unit # Driver
Mailing Address <u>P.O. Box 171</u>			City <u>Gridley</u>		State <u>Ks</u>	Zip Code <u>66852</u>	

Job Type P.T.A. old well Hole Depth _____ Slurry Vol. _____ Tubing _____
Casing Depth _____ Hole Size N/A Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 7" & 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting: WELL WAS ORIGINALLY Completed w/ 7" @ 1784'. 5 1/2 Liner Set @ 1780'. HAS Cement to SURFACE on ANNULUS OF 5 1/2. 5 1/2 PERFORATED @ 850' & @ 250'. RAN 2 3/8 Tubing inside 5 1/2 Spot Cement Plugs AS Following.

20 SKS @ 1735' TAG Cement w/wire Line @ 1598'
6eL SPACER w/ HULLS
20 SKS @ 850' TAG Cement w/wire Line @ 737'
6eL SPACER w/ HULLS
85 SKS 250' to SURFACE

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	785.00	785.00
C 107	35	Mileage	4.20	147.00
C 200	125 SKS	CLASS 'A' Cement	15.75	1968.75
C 205	350 #	CACL2 3%	.63 #	220.50
C 206	300 #	6eL SPACER	.21 #	63.00
C 214	45 #	HULLS	.50 #	22.50
C 108 A	5.87 TONS	TON Mileage	M/c	365.00
C 113	4 HRS	80 BBL VAC TRUCK	90.00	360.00
C 224	3300 gals	CITY WATER	10.00/1000	33.00
			Sub TOTAL	3964.75
			Less 5%	(214.10)
			Sales Tax	314.18
			Total	4064.83

THANK YOU
M

890

Authorization By BRIAN MacLasky Title _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.