

CONSOLIDATED OIL WELL SERVICES, LLC
 P.O. BOX 884, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676



TICKET NUMBER 17274
 LOCATION EURKA
 FOREMAN RICK LEONARD

TREATMENT REPORT & FIELD TICKET
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-12-07	3451	Schomck # 13				Woods
CUSTOMER Haas Petroleum, LLC			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 800 West 47th, Suite 409			463	Kyle		
CITY Kansas City			479	JEFF		
STATE Mo.			452/7-63	J.P.		
ZIP CODE 64112						

JOB TYPE longstring HOLE SIZE 5 1/4" HOLE DEPTH 1015' CASING SIZE & WEIGHT _____
 CASING DEPTH 1000' DRILL PIPE _____ TUBING 2 7/8" OTHER _____
 SLURRY WEIGHT 13.4" SLURRY VOL _____ WATER gal/sk 8.0 CEMENT LEFT in CASING 0'
 DISPLACEMENT 5.8 bbl DISPLACEMENT PSI 500 ~~Rate~~ PSI 900 RATE _____

REMARKS: Safety meeting- Rig up to 2 7/8" tubing. Break circulation w/ 10 bbl fresh water. Pump 4 sks gel-flush, 20 bbl fresh water spacer. Mixed 100 sks thickset cement w/ 4" Kel-seal 1 1/2" @ 13.4" w/c. Washout pump + lines, shut down, release plug. Displace w/ 5.8 bbl fresh water. Final pump pressure 500 PSI. Bump plug to 900 PSI. shut casing in. Good cement returns to surface. Job complete. Rig down

"Thank You"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	840.00	840.00
5406	30	MILEAGE	3.30	99.00
1126A	100 sks	thickset cement	15.40	1540.00
1110A	400 "	Kel-seal 4" 1 1/2"	.38	152.00
1118A	200 "	gel-flush	.15	30.00
5407	5.5	ton-mileage bulk trk	m/c	285.00
4402	1	2 7/8 rubber plug	20.00	20.00
5501C	3 hrs	water transport	100.00	300.00
1123	5000	city water	12.80	64.00
			subtotal	3930.00
			6.3%	SALES TAX
				ESTIMATED TOTAL
				3443.18

212966

AUTHORIZATION Witnessed by Little Joe Greer TITLE _____ DATE _____