

# QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-1071  
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1565

Date	Sec.	Twp.	Range	County	State	On Location	Finish
8-5-19	3	6	22	Graham	Kansas		3:30 PM
Lease <b>TOMANEK</b>				Well No. #1		Owner <b>4 1/2 E 1/4 S INTO</b>	
Contractor <b>FRANK'S Oilfield Service LLC</b>				To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Type Job <b>Plug ABANDONED Well</b>				Charge To <b>NORTHERN LIGHT'S Oil Co. LLC.</b>			
Hole Size <b>8 5/8</b>	T.D.	<b>292</b>		Street			
Csg. <b>5 1/2</b>	Depth	<b>3776</b>		City			
Tbg. Size <b>2 3/8</b>	Depth			State			
Tool <b>PORT COLLAR</b>	Depth	<b>2008</b>		The above was done to satisfaction and supervision of owner agent or contractor.			
Cement Left in Csg.	Shoe Joint			Cement Amount Ordered <b>340 60 40 4% (USED 290 SX)</b>			
Meas Line	Displace			<b>12 Gel 500# HULLS ON SIDE</b>			
<b>EQUIPMENT</b>				Common			
Pumptrk <b>20</b> No.	Cementer	<b>Glenn G.</b>		Poz. Mix			
	Helper	<b>Tony P</b>		Gel.			
Bulktrk <b>21</b> No.	Driver	<b>MIKE P</b>		Calcium			
	Driver			Hulls			
Bulktrk No.	Driver			Salt			
	Driver			Flowseal			
<b>JOB SERVICES &amp; REMARKS</b>				Kol-Seal			
Remarks:				Mud CLR 48			
Rat Hole				CFL-117 or CD110 CAF 38			
Mouse Hole				Sand			
Centralizers				Handling			
Baskets				Mileage			
D/V or Port Collar				<b>Float EQUIPMENT</b>			
<b>Ran 2 3/8 To '3000' Spot 12sx Gel</b>				Guide Shoe			
<b>75sx Cement w/ 200# HULLS,</b>				Centralizer			
<b>2 3/8 @ 2050 Spot 100sx Cement</b>				Baskets			
<b>w/ 300 # HULLS.</b>				AFU Inserts			
<b>2 3/8 @ 1050 - CIRCULATED Cement</b>				Float Shoe			
<b>To Surface w/ 85 SX.</b>				Latch Down			
<b>Pulled 2 3/8 + CAP-OFF w/ 30 SX</b>				Pumptrk Charge			
<b>Cement Hole Stayed Full.</b>				Mileage			
<b>8 5/8 ANNULAS COULD NOT</b>				Tax			
<b>PUMP INTO @ 300 # (HELD)</b>				Discount			
<b>(USED 290 SX)</b>				Total Charge			
<b>THANKS</b>							
X Signature <b>[Signature]</b>							