



PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1012348	1718	04/04/2019
INVOICE NUMBER			
92943515			

Pratt (620) 672-1201
 B YOUNGSTOWN OPERATING LLC
 L 14612 HERTZ QUAIL SPRING PKWY
 L OKLAHOMA CITY
 T OK US 73134
 O ATTN:

J LEASE NAME WasseMiller #1-10
 O LOCATION
 B COUNTY Logan
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41169240			Cash Sale	04/04/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
For Service Dates: 04/03/2019 to 04/03/2019				
0041169240				
171819408L Cement-New Well Casing/Pi 04/03/2019 Cement Surface Casing				
Premium Plus Cement	220.00	EA	6.52	1,434.40 T
Celloflake	55.00	LB	1.48	81.40 T
Calcium Chloride	414.00	LB	0.42	173.88 T
Top Rubber Cement Plug, 8 5/8"	1.00	EA	225.00	225.00
Baffle Plate Aluminum, 8 5/8" (Blue)	1.00	EA	170.00	170.00
Centralizer, 8 5/8" (Blue)	3.00	EA	90.00	270.00
Heavy Equipment Mileage	200.00	MI	3.00	600.00
Blending & Mixing Service Charge	220.00	BAG	0.56	123.20
Proppant & Bulk Del. Chgs., per ton mil	1,035.00	EA	1.00	1,035.00
Depth Charge; 0-500'	1.00	EA	400.00	400.00
Plug Container Utilization Charge	1.00	EA	100.00	100.00
"Unit Mileage Chg (PU, cars one way)"	100.00	MI	1.80	180.00
"Service Supervisor, first 8 hrs on loc.	1.00	EA	70.00	70.00
Cement Data Acquisition Monitor	1.00	EA	220.00	220.00

#9212

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	5,082.88
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	135.17
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	5,218.05
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Youngstown Operating	Cement Pump No.:	37223 19572 12HRS	Operator TRK No.:	78938
Address:		Ticket #:	1718 19572-L 1718 19572-L	Bulk TRK No.:	14355 37724 Corey 14355 37724
City, State, Zip:	AFE#	Job Type:	Z42 - Cement Surface Casing		
Service District:	1718-Liberal KS	Well Type:	OIL		
Well Name and No.:	WasseMiller #1-10	Well Location:	10,11S,34W	County:	Logan
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
Premium Plus Cement	220	2% Calcium Chloride, 1/4# Celloflake	14355 37724 Corey	Front	Back
			14355 37724	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel
Lead:	14.8	1.34	6.33	294.8	TT Man Hours: 39
Tail:					# of Men on Job: 3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
22:00pm							Arrived at location
22:30pm							Spot trucks/Rig up
1:30am							Safety Meeting
1:54am						2000	Pressure test lines to 2000psi
1:56am	4	52.5				200	Pump cement 52.5bbls from 220sks at 14.8#
2:25am							Shut down/Drop plug/Wash pump and lines
2:27am							Start Displacement of 18bbls
2:32am	4	10				200	10bbls gone
2:37am	3	18				500	Bump plug/Hold for 5 minutes
							Check if float holds
							Got 20 bbls of cement to Surface
							Rig Down
							Job Completed
							Thanked the company man and rig crew

Size Hole	12 1/4	Depth	323		TYPE	
Size & Wt. Csg.	8.625 24#	Depth	323	New / Used	Baffle Plate	283
Casing	J-55	Depth			Retainer	Depth
Top Plugs		Type			Perfs	CIBP

Customer Signature:	Basic Representative:	Victor A. Corona
	Basic Signature:	
	Date of Service:	4/3/2019