


810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4700**
 Foreman Kevin McCoy
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
8-29-19	1008	BARKER #3	2	255	8E	GW	KS	
Customer <u>JACKSON BROTHERS LLC</u>			Safety Meeting <u>KM AM 5M 6M</u>		Unit #	Driver	Unit #	Driver
Mailing Address <u>116 E. 3RD</u>					<u>104</u>	<u>ALAN M.</u>		
City <u>EUREKA</u>			State <u>KS</u>		<u>110</u>	<u>KEVIN M.</u>		
Zip Code <u>67045</u>					<u>145</u>	<u>STEVE M.</u>		
					<u>Helper</u>	<u>GREG M.</u>		

Job Type P.T.A. old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8 & 1"
 Casing Depth _____ Hole Size 7 7/8 Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY MEETING: RAN 2 3/8 TUBING TO 1050' INSIDE 4 1/2 CASING. PUMP 300# GEL SPACER. SPOT 20 SKS CEMENT @ 1050'. PULL TUBING. BUILD BRIDGE PLUG @ 275' IN 4 1/2. (BOTTOM PLUG WAS SET BY LONG DRILG. CO. 4 1/2 WAS PERFORATED @ 1050' & @ 250') RIG UP TO 4 1/2 CASING, COULD NOT CIRCULATE FLUID TO SURFACE THRU PERFS @ 250'. ANNULUS & 4 1/2 ID BOTH STANDING FULL OF WATER. RAN 1" HYDRILL TUBING DOWN ANNULUS OF 4 1/2 TO 256' W/ NO RESTRICTIONS. SPOT SOLID CEMENT PLUG FROM 256' TO SURFACE W/ 67 SKS CEMENT. ANNULUS STANDING FULL OF CEMENT. PULL 1" TUBING. RAN 1" HYDRILL TUBING DOWN ID OF 4 1/2 TO 256'. SPOT SOLID CEMENT PLUG FROM 256' TO SURFACE. PULL 1" TUBING, TOP OFF 4 1/2 W/ CEMENT. = 20 SKS CEMENT FOR TOP PLUG ON ID OF 4 1/2. 4 1/2 ID STANDING FULL OF CEMENT. JOB COMPLETE. RIG DOWN.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	785.00	785.00
C 107	15	Mileage	4.20	63.00
C 203	107 SKS	60/40 Pozmix Cement	13.40	1433.80
C 206	370 *	Gel 4%	.21 *	77.70
C 206	300 #	Gel SPACER	.21 *	63.00
C 108 A	4.60 TONS	TON Mileage	M/C	365.00
C 113	4 HRS	80 BBL VAC TRUCK	90.00	360.00
			Sub-TOTAL	3147.50
			Less 5%	169.97
			SALES TAX	251.80
			8.0%	

THANK YOU
~~MA~~

Authorization Roscoe H. Jackson II Title CO-MANAGER Total 3229.33

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.