



### Job Log


Customer:	Youngstown Operating LLC	Cement Pump No.:	38119-19570 7 HRS	Operator TRK No.:	96815
Address:	14612 Hertz Quail Springs Parkway	Ticket #:	1718-19391 L	Bulk TRK No.:	27808-19883
City, State, Zip:	Oklahoma City, Ok 73134	Job Type:	Z42 Production Casing		
Service District:		Well Type:	OIL		
Well Name and No.:	WasseMiller #1-10	Well Location:	10-11S-34W	County:	Logan State: Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
A-CON BLEND	50	3%CaCl, 1/4#POLYFLAKE	27808-19883	Front	Back
50/50 POZ	135	5%GYPSUM, 10%SALT, 5#GILSONITE, .5%C-17, 1/4#DEFOAMER		Front	Back
				Front	Back


Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
<b>Lead:</b>	11.4	2.95	18.1	147.5	Man Hours:	37
<b>Tail:</b>	13.8	1.49	6.65	201.15	# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
8:00							ON LOC, SAFTEY MTG, R.U.
14:40						2500	TEST LINES
2:40 PM	5.5	12				130	PUMP MUD FLUSH
2:45 PM	5.5	5				130	H2O SPACER
2:50 PM							PLUG RAT HOLE
14:58	7					260	START SCAVENGER @ 11.4#
15:00	7	13				210	ON 50/50 POZ @ 13.8#
3:10 PM		36					SHUT DOWN, DROP PLUG, WASHUP
15:15	7					80	START DISPLACEMENT
15:29	2.9	92				300	SLOW RATE
15:37		112.6				680-1420	PLUG DOWN
15:40							RELEASED PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	9 7/8	Depth		TYPE	
Size & Wt. Csg.	5 1/2 19.5	Depth	4772.6	Packer	Depth
fbg.		Depth		Retainer	Depth
Top Plugs		Type		Perfs	CIBP

Customer Signature: 

Basic Representative: CHAD HINZ

Basic Signature: 

Date of Service: 4/12/2010

YOUNGSTOWN  
WMI 1-10

