

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: _____
 Name: _____
 Address 1: _____
 Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Contact Person: _____
 Phone: (_____) _____
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - _____
 Spot Description: _____
 _____ - _____ - _____ - _____ Sec. _____ Twp. _____ S. R. _____ East West
 _____ Feet from North / South Line of Section
 _____ Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: _____
 Lease Name: _____ Well #: _____
 Date Well Completed: _____
 The plugging proposal was approved on: _____ (Date)
 by: _____ (KCC District Agent's Name)
 Plugging Commenced: _____
 Plugging Completed: _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging Contractor License #: _____ Name: _____
 Address 1: _____ Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Phone: (_____) _____
 Name of Party Responsible for Plugging Fees: _____
 State of _____ County, _____, ss.
 _____ Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

BLUE STAR ACID SERVICE, INC.

PO Box 93
Eureka, Kansas 67045

Cementing Ticket
and Invoice Number

Nº 001775

Date 8-12-98	Customer Order No.	Sec't 2	Trwp 25	Range 8E	Truck Called Out —	On Location 9:00 AM	Job Began 9:30 AM	Job Completed 12:00 PM
Owner Jackson Brothers		Contractor M ^c Coy Well Serv.			Charge To Jackson Brothers			
Mailing Address 514 N. Main		City Eureka			State Kansas 67045			
Well No. & Form Barker # 2		Place		County Greenwood		State Kansas		
Depth of Well 968'		Casing (New) (Used)	Size 4 1/2"		Size of Hole Amt. and Kind 6 3/4 200 SKS.		Cement Left in casing by Request Necessity 28' feet	
Kind of Job Bull Head Squeeze			Weight		Drillpipe Tubing		Rotary Cable Truck No. Unit # 2	

Price Reference No. # 1
Price of Job 665.00
Second Stage
Mileage 127 25.20
Other Charges
Total Charges 690.20


Remarks
Rig up to 4 1/2" casing, pump onto well with 400 P.S.I.
we had pumped 20 Bbls. we had circulation on Annulus.
After it had circulated for a while Pressure dropped off to 300 P.S.I.
we Staged hole at 968', when Flgs hit Pressure increased,
Mix 200 lbs. Gek. To Flush hole ahead of cement
Mix 200 SKS. Regular cement with 2% Gek, shutdown
washout Pump + Lines. - Release Plug - Displace Plug with 15 Bbls.
Final pumping at 600 P.S.I. shutdown with 300 P.S.I.
Leaving Plug at 940', after 5 mins. Plug stayed at 940'
close casing in with 300 P.S.I.

Cementer Bradley Butler - Job complete with good cement returns.
Helper Russell M^cCoy District Eureka State Kansas
The above job was done under supervision of the owner, operator, or his agent whose signature appears below.
"Thank you" x Roscoe H. Jackson II
Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
200	SKS. Regular cement	5.75	1150.00
375	lbs. Gek 2%	8.60	32.25
200	lbs. Gek Flush Ahead	8.60	17.20
1	4 1/2" Rubber Plug	25.00	25.00
	200 SKS. Handling & Dumping	.50	100.00
	9.5 Ton Mileage 12	.70	79.80
	Sub Total		2094.45
	Delivered by Truck No. Unit # 3		Discount
	Delivered from Eureka	Sales Tax 5.9%	123.57
	Signature of operator Brad Butth	Total	2218.02

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4724**
 Foreman David Gardner
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-12-19	1008	Barker #2	2	25S	8E	Greenwood	KS
Customer			Unit #	Driver	Unit #	Driver	
Jackson Brothers LLC			105	Jason			
Mailing Address			115	Zevi			
116 E. 3 rd			145	Steve			
City	State	Zip Code					
Eureka	KS	67045					

Job Type P.T.A. old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8" + 1"
 Casing Depth _____ Hole Size 6 3/4" Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 2 3/8" Tubing. Plug well as follows:
4 1/2" Perforated @ 1050' + 250'.
Bottom Plug set by Long Drlg.
20 SKS @ 1050'
Gel Spacer
30 SKS @ 250' to surface inside 4 1/2".
Ran 1" Hydrill tubing down 4 1/2" annulus + tagged cement @ 8'. Top off w/ 5 SKS cement.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	785.00	785.00
C107	15	Mileage	4.20	63.00
C203	55 SKS	60/40 Pozmix Cement	13.40	737.00
C206	190 #	Gel @ 4%	.21	39.90
C108A	2.365 Tons	Ton Mileage - Bulk Truck	m/c	365.00
C206	300 #	Gel Spacer	.21	63.00
C113	2 HRS.	80 Bbl Vac Truck	90.00 /HR	180.00
<u>Thank You</u>				
			Sub Total	2,232.90
			Less 5%	115.00
			Sales Tax	67.19
			8.0%	

Authorization Roscoe Jackson II Title Co-MANAGER Total 2,185.09 **OK**

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.