

SWIFT Services, Inc.

DATE 8-28-19	PAGE NO.
TICKET NO. 032547	

WELL NO. Viking Resources		LEASE Ramsey Z		JOB TYPE PTA		DESCRIPTION OF OPERATION AND MATERIALS	
CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)	
				T	C	TUBING	CASING
	1100						On Location 2 3/8" 4 1/2"
	1120	1/2	1		✓	300	Plug 8 5/8 w/ 5 sks of 60/40 Pozmix 4% gel @ 13.1 ppg
	1130	3 1/2	13	✓		150	Plug @ 4473' w/ 150# of hulls + 50 sks of 60/40 Poz
		4	12	✓		150	Displace CMT Pull 70 Joints
	1250	4	37	✓		400	Plug @ 2250' w/ 140 sks - Circulate to Surface TOH
	1400				✓		Top off @ 4 1/2" w/ 20 sks
	1415						Wash up Trk #112
	1430						Job Complete 215 sks used Total 150 lbs of Cotton Seed hulls used Thank You Gideon, Preston, Shane

