



PRESSURE PUMPING LLC  
PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

100457  
400057

TICKET NUMBER 56112  
LOCATION Oaklawn  
FOREMAN Walt Driskol

FIELD TICKET & TREATMENT REPORT  
CEMENT

Invoice # 900791

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
4-24-19	7251	Great Bend Trust #1-7	7	15 <sup>0</sup>	41 <sup>W</sup>	Wallace	
CUSTOMER		MAILING ADDRESS		TRUCK #	DRIVER	TRUCK #	DRIVER
Red Oak Energy		7701 E. Kellogg Dr., Ste. 710		731	Cory Davis		
CITY		STATE	ZIP CODE	528-1129	Kaleb Crompton - Kanner Colby		
Wichita		KS	67207-1705	1098	Walt Driskol		

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 618 CASING SIZE & WEIGHT 8 5/8 - 23#  
 CASING DEPTH 618' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 12.5-14.8 SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 40'  
 DISPLACEMENT 35 1/2 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4 BPM

REMARKS: Safety meeting, Rig up on Murfin #21, Circ casing on Bottom  
mix 225 sks 65/35 conc, 6% lat, 3% cc, Tail in with 150 sks conc, 3% cc - 2% lat  
release Plug & Displace 35 1/2 BBL H<sub>2</sub>O, Land Plug & shut in  
500#  
Cement Dial Circ  
Approx 10 BBL to RT

Thank You  
Walt + Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
Co0471	1	PUMP CHARGE	1,150.00	1,150.00
Co0002	40	MILEAGE	7.15	286.00
Co0710	16.84	Ton Mileage Delivery	67.5	1,178.80
Co5871	150 SKS	Surface Blend II	24.00	3600.00
Co5829	225 SKS	Lite Weight Blend IV	19.50	4,387.50
CP8453	1	8 5/8 Baffle Plate	162.00	162.00
CP8556	3	8 5/8 Centralizers	110.00	330.00
CP8181	1	8 5/8 Rubber Plug	185.00	185.00
				11,279.20
		Less 25% Disc	-	2,819.83
				8,459.37
		SALES TAX		487.37
		ESTIMATED TOTAL		8946.85

RAVIN 3737  
 AUTHORIZATION Juan Davis TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form