

GEOLOGIST'S REPORT
DRILLING TIME AND SAMPLE LOG

Table with 2 columns: COMPANY (VESS OIL CORPORATION), LEASE (WILSON 'A' #456), FIELD (EL DORADO), LOCATION (330' FSL & 2500' FWL), SECTION (8), TOWNSHIP (25S), RANGE (05E), COUNTY (BUTLER), STATE (KANSAS). Right column: ELEVATIONS (KB 1385', GL 1376'), Measurements Are All From KB, API # 15-015-24125-0000.

CONTRACTOR: C&G DRILLING, RIG #2. SPUD: 07/09/2019. COMP: 07/13/2019. RTD: 2480'. LTD: n/a. SURFACE: 6.16 x 8.58" 240' 1.35 wt @ 254'. PRODUCTION: 69 jls 5.12" 15.660 m. MW-55 wt @ 2478' w/10 cc x15C.

FORMATION TOPS, LOG, SAMPLES, CHRONOLOGY. Includes ADMIRE 658 SS, WHITE CLOUD LS, WHITE CLOUD SD, OREAD, HEBNER, DOUGLAS SD, LANSING, KANSAS CITY, BASE KANSAS CITY, CHECKERBOARD, CHELSEA SD, ALFAMONT, CHEROKEE, ARDMORE, VIOLA, RTD.

REMARKS: 07/13/2019- RHH w/packer hose, 89 jls 5.12", 14.560 m MW-55 casing w/basket 7 centralizers (centralizers on #1, 2, 8, 10, 12, 16 & 24. Basket on 2nd collar). Tagged solid bottom, picked up 2', dropped ball and set packer above. Cite hole for 2 hr 150 plugged monohole and radwell w/10 cc x15, production casing w/ 150 cc 15C mixed @ 144 ppg. Lift pressure of 460 psi w/eng pressure of 250 psi, released pressure w/ 1.5th bbl back to truck. Float equipment held.

Table with 2 columns: SAMPLE DESCRIPTION and REMARKS. Contains detailed geological descriptions and notes for various depths.



