

QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-1071
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1550

Date	Sec.	Twp.	Range	County	State	On Location	Finish
7-14-19	2	11	17	Ellis	KS		

Location Cadell RD. + River RD Jct. 1 N

Lease Slimmer Well No. #1 Owner W/E N into

Contractor White Knight Dols. To Quality Oilwell Cementing, Inc.
Type Job Port Collor You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Hole Size 7 7/8 T.D. 3536' Charge To Anchor Bay Petroleum LLC

Csg. 5 1/2 #15.5 Depth 3488.85 Street

Tbg. Size Depth City State

Tool Port Collor Depth 1121.16' The above was done to satisfaction and supervision of owner agent or contractor.

Cement Left in Csg. ☒ Shoe Joint 42.05' Cement Amount Ordered 180SK com + 10Y. SALT

Meas Line Displace 82^{bu}/H₂O + 5Y. Gil (500gal) mud flush

EQUIPMENT Common /80

Pumptrk #17 No. Cementer Tony P Helper Rick Poz. Mix

Bulktrk No. Driver Jade Driver Jade Gel.

Bulktrk 15 No. Driver Jade Driver Jade Calcium

JOB SERVICES & REMARKS Halls

Remarks: USED: 180SK 10Y. SALT Salt 15

Rat Hole 30SK Flowseal

Mouse Hole 0 Kol-Seal 800#

Centralizers 1, 2, 6, 11, 17 Mud CLR 48 500 gal

Baskets 4, 5, 7 CFL-117 or CD110 CAF 38

D/V or Port Collar 58 - 1121.16' Sand

* Ran Csg 5 1/2 @ 3488.85' Handling 203

* Broke circulation. Mileage

* 500 gal mud flush + 20^{bu} ahead

* 30SK RAT Hole

* 180SK com 10Y. SALT + 5Y. Gil

* Cleared lines

* Displaced cement @ 82^{bu} H₂O

* landed 5/8" plug @ #1500 ps.

* Released Back OK

Thanks

Pumptrk Charge prod string

Mileage 24

Signature [Signature] Tax

Discount

Total Charge