

JOB LOG

SWIFT Services, Inc.

DATE 8-22-19	PAGE NO. 1
TICKET NO. 032544	

CUSTOMER Mull Drlg Co	WELL NO. 1-4	LEASE Comstock	JOB TYPE PTA
--------------------------	-----------------	-------------------	-----------------

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1330							On Location 4 1/2 10.516/19
	1345	3 1/2	65				150	Lead Hole
	1410	3 1/2	13				150	Plug @ 1220' w/ 50 sks of 60/40 Pozmix @ 13.1 ppg
		3 1/2	10				150	Displace CMT - Pull 9 Joints
	1440	3 1/2	13				150	Plug @ 865' w/ 50 sks
		3 1/2	7				150	Displace CMT - Pull 11 JTs
	1510	3 1/2	13				100	Plug @ 415' w/ 50 sks
		3 1/2	3				100	Displace CMT - Pull 9 JTs
	1535	3 1/2	3				75	Plug @ 60' w/ 10 sks - Circulate CMT to Surface TOH
	1550	1/2	1				0	Top off w/ 5 sks
								Wash up Trk #112
	1615							Job Complete
								165 sks of 60/40 Pozmix 4 1/2 gal used
								Thank You
								Gideon, Preston, Kirdge