



RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

Weber 6-1

			Start 7-23-19
			Finish 7-24-19
9	soil	9	
23	clay/gravel	32	
213	shale	245	
44	lime	289	
12	shale	301	
42	lime	343	
75	shale	418	
105	lime	523	Set 40' 7" w/5sxs
25	shale	548	Plugged 8/6/19
127	lime	675	Ran 1" to 1050' pumped in
172	shale	847	15sxs. Pulled up to 600'
30	lime	877	pumped in 15sxs. Pulled up
59	shale	936	to 250' filled well to surface
32	lime	968	30sxs. 60 sxs total
15	shale	983	
6	lime	989	
14	shale	1003	
7	lime	1010	
6	shale	1016	
3	lime	1019	
8	shale	1027	
2	bkn sand	1029	
32	shale	1061	
4	sandy shale	1065	
15	shale	1080	T.D. dry