



RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

Webber #2

			Start 7-26-19
			Finish 7-30-19
7	soil	7	
28	clay/gravel	35	
206	shale	241	
40	lime	281	
18	shale	299	
39	lime	338	
80	shale	418	
100	lime	518	Set 40' 7" w/ 5sxs
29	shale	547	Ran 1103' of 2 7/8
130	lime	677	cemented to the surface
168	shale	845	135sxs
35	lime	880	
49	shale	929	
32	lime	961	
15	shale	976	
10	lime	986	
11	shale	997	
6	lime	1003	
6	shale	1009	
6	lime	1015	
7	shale	1022	
9	sandy shale	1031	show
23	shale	1054	
7	oil sand	1061	good show
3	dk sand	1064	show
46	shale	1110	T.D.